



CITY OF ABSECON
Municipal Complex
500 Mill Road
Absecon, New Jersey 08201

Carie A. Crone, RMC
Municipal Clerk

Phone (609) 641-0663 x101
Fax (609) 645-5098

CITY COUNCIL

JANUARY 18th, 2024

REGULAR MEETING - 6:30 PM

AGENDA

FLAG SALUTE

ROLL CALL

PRESIDENT'S STATEMENT ON THE SUNSHINE LAW

NOTIFICATION THAT THIS MEETING IS ELECTRONICALLY RECORDED

REGULAR MEETING AGENDA

2024 ORDINANCES FOR INTRODUCTION

- 01** Amending the Code of the City of Absecon, Chapter 224 – Land Use and Development, Article XXXV – Stormwater Control.
- 02** Amending the Code of the City of Absecon, creating Chapter 259 – Privately-owned Salt Storage.
- 03** Amending the Code of the City of Absecon, Chapter 3 – Administrative Code, Article 1 – Mayor and Council, Section 3-1- Council Committees.

CONSENT AGENDA

- 29 Appointing a Public Works Laborer/Operator, namely Thomas Andrews.
- 30 Permitting a Charitable Organization to solicit funds, namely the Absecon VFW Post 9462 Auxiliary.
- 31 Permitting a Charitable Organization to solicit funds, namely the Charles A. Hammell Post 28 American Legion.
- 32 Permitting a Charitable Organization to solicit funds, namely the Absecon Green Team.
- 33 Authorizing the submission of the City of Absecon's Tonnage Grant Application for the year 2023 to the New Jersey Department of Environmental.
- 34 Authorizing the Tax Collector to prorate and cancel 4th quarter taxes of 2023 and cancel the 2024 preliminary on the property located at 1009 Caralena Court.
- 35 Authorizing the Tax Collector to prorate and refund 3rd quarter taxes of 2023 and cancel and refund 4th quarter and the 2024 preliminary on the property located at 1 Claridge Court.
- 36 Extending the Grant Agreement term with the State of New Jersey Local Efficiency Achievement Program (LEAP).
- 37 Authorizing the Mayor to enter into a second amended Interlocal Agreement with Atlantic County regarding flashing signal equipment at various locations.
- 38 Authorizing the Mayor to enter into a License Agreement/Hold Harmless Agreement with Atlantic County concerning Streetscape Improvements within the County Right of Way of New Jersey Ave.
- 39 Authorizing the Mayor and other City Official to execute the 2024 Safety Contract with the Atlantic County Municipal Joint Insurance Fund.
- 40 Authorizing the transfer of appropriation reserves in the 2023 local municipal budget per N.J.S.A. 40A; 4-59.
- 41 Reconstituting the Green Team Advisory Committee for the City of Absecon.
- 42 Recognizing the members of the Absecon Green Team, a task force for sustainable Absecon.

APPROVAL OF BILL LIST - \$ 1,691,413.78

APPROVAL OF MINUTES

Regular Meeting Minutes – 12/21/2023

Re-Organization Minutes – 1/4/2024

REPORTS Council Committees
Administrator/CFO
Clerk
Mayor
Engineer

PUBLIC PORTION

CLOSED SESSION - #43 – Contract Negotiations

ADJOURNMENT

CITY OF ABSECON

ORDINANCE 01-2024

**AN ORDINANCE AMENDING THE CODE OF THE CITY OF ABSECON, CHAPTER 224
LAND USE DEVELOPMENT ARTICLE XXXV STORMWATER CONTROL**

NOW THEREFORE BE IT ORDAINED by the Common Council of the City of Absecon,
County of Atlantic and State of New Jersey as follows:

**Absecon City Code Chapter 224 Land Use Development Article XXXV Stormwater
Control shall be amended as follows:**

§ 224-311. Scope and Purpose:

A. Policy Statement

Flood control, groundwater recharge, and pollutant reduction shall be achieved through the use of stormwater management measures, including green infrastructure Best Management Practices (GI BMPs) and nonstructural stormwater management strategies. GI BMPs and low impact development (LID) should be utilized to meet the goal of maintaining natural hydrology to reduce stormwater runoff volume, reduce erosion, encourage infiltration and groundwater recharge, and reduce pollution. GI BMPs and LID should be developed based upon physical site conditions and the origin, nature and the anticipated quantity, or amount, of potential pollutants. Multiple stormwater management BMPs may be necessary to achieve the established performance standards for water quality, quantity, and groundwater recharge.

B. Purpose

The purpose of this Article is to establish minimum stormwater management requirements and controls for "major development," as defined below in § 224-312.

C. Applicability

1. This Article shall be applicable to the following major developments:

- a. Non-residential major developments; and
- b. Aspects of residential major developments that are not pre-empted by the Residential Site Improvement Standards at N.J.A.C. 5:21.

2. This Article shall also be applicable to all major developments undertaken by the City of Absecon.

3. An application required by this Article pursuant to (b)1 above that has been submitted prior to **December 21, 2023**, shall be subject to the stormwater management requirements in effect on December 20, 2023.

4. An application required by this Article for approval pursuant to (b)1 above that has been submitted on or after March 2, 2021, but prior to December 21, 2023, shall be subject to the stormwater management requirements in effect on December 13, 2023.

5. Notwithstanding any rule to the contrary, a major development for any public roadway or railroad project conducted by a public transportation entity that has determined a preferred alternative or reached an equivalent milestone before July 17, 2023, shall be subject to the stormwater management requirements in effect prior to July 17, 2023.

D. Compatibility with Other Permit and Ordinance Requirements

Development approvals issued pursuant to this Article are to be considered an integral part of development approvals and do not relieve the applicant of the responsibility to secure required permits or approvals for activities regulated by any other applicable code, rule, act, or ordinance. In their interpretation and application, the provisions of this Article shall be held to be the minimum requirements for the promotion of the public health, safety, and general welfare.

This Article is not intended to interfere with, abrogate, or annul any other ordinances, rule or regulation, statute, or other provision of law except that, where any provision of this Article imposes restrictions different from those imposed by any other ordinance, rule or regulation, or other provision of law, the more restrictive provisions or higher standards shall control.

§ 224-312. Definitions:

For the purpose of this Article, the following terms, phrases, words and their derivations shall have the meanings stated herein unless their use in the text of this Article clearly demonstrates a different meaning. When not inconsistent with the context, words used in the present tense include the future, words used in the plural number include the singular number, and words used in the singular number include the plural number. The word "shall" is always mandatory and not merely directory. The definitions below are the same as or based on the corresponding definitions in the Stormwater Management Rules at N.J.A.C. 7:8-1.2.

"CAFRA Centers, Cores or Nodes" means those areas with boundaries incorporated by reference or revised by the Department in accordance with N.J.A.C. 7:7-13.16.

"CAFRA Planning Map" means the map used by the Department to identify the location of Coastal Planning Areas, CAFRA centers, CAFRA cores, and CAFRA nodes. The CAFRA Planning Map is available on the Department's Geographic Information System (GIS).

"Community basin" means an infiltration system, sand filter designed to infiltrate, standard constructed wetland, or wet pond, established in accordance with N.J.A.C. 7:8-4.2(c)14, that is designed and constructed in accordance with the New Jersey Stormwater Best Management Practices Manual, or an alternate design, approved in accordance with N.J.A.C. 7:8-5.2(g), for an infiltration system, sand filter designed to infiltrate, standard constructed wetland, or wet pond and that complies with the requirements of this Article.

"Compaction" means the increase in soil bulk density.

"Contributory drainage area" means the area from which stormwater runoff drains to a stormwater management measure, not including the area of the stormwater management measure itself.

"Core" means a pedestrian-oriented area of commercial and civic uses serving the surrounding municipality, generally including housing and access to public transportation.

"County review agency" means an agency designated by the County Commissioners to review municipal stormwater management plans and implementing ordinance(s). The county review agency may either be:

1. A county planning agency or
2. A county water resource association created under N.J.S.A 58:16A-55.5, if the ordinance or resolution delegates authority to approve, conditionally approve, or disapprove municipal stormwater management plans and implementing ordinances.

“Department” means the Department of Environmental Protection.

“Designated Center” means a State Development and Redevelopment Plan Center as designated by the State Planning Commission such as urban, regional, town, village, or hamlet.

“Design engineer” means a person professionally qualified and duly licensed in New Jersey to perform engineering services that may include, but not necessarily be limited to, development of project requirements, creation and development of project design and preparation of drawings and specifications.

“Development” means the division of a parcel of land into two or more parcels, the construction, reconstruction, conversion, structural alteration, relocation or enlarge-enlargement of any building or structure, any mining excavation or landfill, and any use or change in the use of any building or other structure, or land or extension of use of land, for which permission is required under the Municipal Land Use Law, N.J.S.A. 40:55D-1 *et seq.*

In the case of development of agricultural land, development means: any activity that requires a State permit, any activity reviewed by the County Agricultural Board (CAB) and the State Agricultural Development Committee (SADC), and municipal review of any activity not exempted by the Right to Farm Act , N.J.S.A 4:1C-1 *et seq.*

“Disturbance” means the placement or reconstruction of impervious surface or motor vehicle surface, or exposure and/or movement of soil or bedrock or clearing, cutting, or removing of vegetation. Milling and repaving is not considered disturbance for the purposes of this definition.

“Drainage area” means a geographic area within which stormwater, sediments, or dissolved materials drain to a particular receiving waterbody or to a particular point along a receiving waterbody.

“Environmentally constrained area” means the following areas where the physical alteration of the land is in some way restricted, either through regulation, easement, deed restriction or ownership such as: wetlands, floodplains, threatened and endangered species sites or designated habitats, and parks and preserves. Habitats of endangered or threatened species are identified using the Department's Landscape Project as approved by the Department's Endangered and Nongame Species Program.

“Environmentally critical area” means an area or feature which is of significant environmental value, including but not limited to: stream corridors, natural heritage priority sites, habitats of endangered or threatened species, large areas of contiguous open space or upland forest, steep slopes, and well head protection and groundwater recharge areas. Habitats of endangered or threatened species are identified using the Department’s Landscape Project as approved by the Department’s Endangered and Nongame Species Program.

“Empowerment Neighborhoods” means neighborhoods designated by the Urban Coordinating Council “in consultation and conjunction with” the New Jersey Redevelopment Authority pursuant to N.J.S.A 55:19-69.

“Erosion” means the detachment and movement of soil or rock fragments by water, wind, ice, or gravity.

“Green infrastructure” means a stormwater management measure that manages stormwater close to its source by:

1. Treating stormwater runoff through infiltration into subsoil;
2. Treating stormwater runoff through filtration by vegetation or soil; or
3. Storing stormwater runoff for reuse.

"HUC 14" or "hydrologic unit code 14" means an area within which water drains to a particular receiving surface water body, also known as a subwatershed, which is identified by a 14-digit hydrologic unit boundary designation, delineated within New Jersey by the United States Geological Survey.

"Impervious surface" means a surface that has been covered with a layer of material so that it is highly resistant to infiltration by water.

"Infiltration" is the process by which water seeps into the soil from precipitation.

"Lead planning agency" means one or more public entities having stormwater management planning authority designated by the regional stormwater management planning committee pursuant to N.J.A.C. 7:8-3.2, that serves as the primary representative of the committee.

"Major development" means an individual "development," as well as multiple developments that individually or collectively result in:

1. The disturbance of one or more acres of land since February 2, 2004;
2. The creation of one-quarter acre or more of "regulated impervious surface" since February 2, 2004;
3. The creation of one-quarter acre or more of "regulated motor vehicle surface" since March 2, 2021; or
4. A combination of 2 and 3 above that totals an area of one-quarter acre or more. The same surface shall not be counted twice when determining if the combination area equals one-quarter acre or more.

Major development includes all developments that are part of a common plan of development or sale (for example, phased residential development) that collectively or individually meet any one or more of paragraphs 1, 2, 3, or 4 above. Projects undertaken by any government agency that otherwise meet the definition of "major development" but which do not require approval under the Municipal Land Use Law, N.J.S.A. 40:55D-1 et seq., are also considered "major development."

"Motor vehicle" means land vehicles propelled other than by muscular power, such as automobiles, motorcycles, autocycles, and low speed vehicles. For the purposes of this definition, motor vehicle does not include farm equipment, snowmobiles, all-terrain vehicles, motorized wheelchairs, go-carts, gas buggies, golf carts, ski-slope grooming machines, or vehicles that run only on rails or tracks.

"Motor vehicle surface" means any pervious or impervious surface that is intended to be used by "motor vehicles" and/or aircraft, and is directly exposed to precipitation including, but not limited to, driveways, parking areas, parking garages, roads, race-tracks, and runways.

"Municipality" means any city, borough, town, township, or village.

"New Jersey Stormwater Best Management Practices (BMP) Manual" or "BMP Manual" means the manual maintained by the Department providing, in part, design specifications, removal rates, calculation methods, and soil testing procedures approved by the Department as being capable of contributing to the achievement of the stormwater management standards specified in this Article. The BMP Manual is periodically amended by the Department as necessary to provide design specifications on additional best management practices and new information on already included practices reflecting the best available current information regarding the particular practice and the Department's determination as to the ability of that best management practice to contribute to compliance with the standards contained in this Article. Alternative stormwater management measures, removal rates, or calculation methods may be utilized, subject to any limitations specified in this Article, provided the design engineer demonstrates to the municipality, in accordance with § 224-4.F. of this Article and N.J.A.C. 7:8-5.2(g), that the proposed measure and its design will contribute to achievement of the design and performance standards established by this Article.

“Node” means an area designated by the State Planning Commission concentrating facilities and activities which are not organized in a compact form.

“Nutrient” means a chemical element or compound, such as nitrogen or phosphorus, which is essential to and promotes the development of organisms.

“Person” means any individual, corporation, company, partnership, firm, association, political subdivision of this State and any state, interstate or Federal agency.

“Pollutant” means any dredged spoil, solid waste, incinerator residue, filter backwash, sewage, garbage, refuse, oil, grease, sewage sludge, munitions, chemical wastes, biological materials, medical wastes, radioactive substance (except those regulated under the Atomic Energy Act of 1954, as amended (42 U.S.C. §§ 2011 *et seq.*)), thermal waste, wrecked or discarded equipment, rock, sand, cellar dirt, industrial, municipal, agricultural, and construction waste or runoff, or other residue discharged directly or indirectly to the land, ground waters or surface waters of the State, or to a domestic treatment works. “Pollutant” includes both hazardous and nonhazardous pollutants.

“Public roadway or railroad” means a pathway for use by motor vehicles or trains that is intended for public use and is constructed by, or on behalf of, a public transportation entity. A public roadway or railroad does not include a roadway or railroad constructed as part of a private development, regardless of whether the roadway or railroad is ultimately to be dedicated to and/or maintained by a governmental entity.

“Public transportation entity” means a Federal, State, county, or municipal government, an independent State authority, or a statutorily authorized public-private partnership program pursuant to P.L. 2018, c. 90 (N.J.S.A. 40A:11-52 *et seq.*), that performs a public roadway or railroad project that includes new construction, expansion, reconstruction, or improvement of a public roadway or railroad.

“Recharge” means the amount of water from precipitation that infiltrates into the ground and is not evapotranspired.

“Regulated impervious surface” means any of the following, alone or in combination:

1. A net increase of impervious surface;
2. The total area of impervious surface collected by a new stormwater conveyance system (for the purpose of this definition, a “new stormwater conveyance system” is a stormwater conveyance system that is constructed where one did not exist immediately prior to its construction or an existing system for which a new discharge location is created);
3. The total area of impervious surface proposed to be newly collected by an existing stormwater conveyance system; and/or
4. The total area of impervious surface collected by an existing stormwater conveyance system where the capacity of that conveyance system is increased.

“Regulated motor vehicle surface” means any of the following, alone or in combination:

1. The total area of motor vehicle surface that is currently receiving water;
2. A net increase in motor vehicle surface; and/or
quality treatment either by vegetation or soil, by an existing stormwater management measure, or by treatment at a wastewater treatment plant, where the water quality treatment will be modified or removed.

“Sediment” means solid material, mineral or organic, that is in suspension, is being transported, or has been moved from its site of origin by air, water or gravity as a product of erosion.

“Site” means the lot or lots upon which a major development is to occur or has occurred.

“Soil” means all unconsolidated mineral and organic material of any origin.

“State Development and Redevelopment Plan Metropolitan Planning Area (PA1)” means an area delineated on the State Plan Policy Map and adopted by the State Planning Commission that is intended to be the focus for much of the State’s future redevelopment and revitalization efforts.

“State Plan Policy Map” is defined as the geographic application of the State Development and Redevelopment Plan’s goals and statewide policies, and the official map of these goals and policies.

“Stormwater” means water resulting from precipitation (including rain and snow) that runs off the land’s surface, is transmitted to the subsurface, or is captured by separate storm sewers or other sewage or drainage facilities, or conveyed by snow removal equipment.

“Stormwater management BMP” means an excavation or embankment and related areas designed to retain stormwater runoff. A stormwater management BMP may either be normally dry (that is, a detention basin or infiltration system), retain water in a permanent pool (a retention basin), or be planted mainly with wetland vegetation (most constructed stormwater wetlands).

“Stormwater management measure” means any practice, technology, process, program, or other method intended to control or reduce stormwater runoff and associated pollutants, or to induce or control the infiltration or groundwater recharge of stormwater or to eliminate illicit or illegal non-stormwater discharges into stormwater conveyances.

“Stormwater runoff” means water flow on the surface of the ground or in storm sewers, resulting from precipitation.

“Stormwater management planning agency” means a public body authorized by legislation to prepare stormwater management plans.

“Stormwater management planning area” means the geographic area for which a stormwater management planning agency is authorized to prepare stormwater management plans, or a specific portion of that area identified in a stormwater management plan prepared by that agency.

“Tidal Flood Hazard Area” means a flood hazard area in which the flood elevation resulting from the two-, 10-, or 100-year storm, as applicable, is governed by tidal flooding from the Atlantic Ocean. Flooding in a tidal flood hazard area may be contributed to, or influenced by, stormwater runoff from inland areas, but the depth of flooding generated by the tidal rise and fall of the Atlantic Ocean is greater than flooding from any fluvial sources. In some situations, depending upon the extent of the storm surge from a particular storm event, a flood hazard area may be tidal in the 100-year storm, but fluvial in more frequent storm events.

“Urban Coordinating Council Empowerment Neighborhood” means a neighborhood given priority access to State resources through the New Jersey Redevelopment Authority.

“Urban Enterprise Zones” means a zone designated by the New Jersey Enterprise Zone Authority pursuant to the New Jersey Urban Enterprise Zones Act, N.J.S.A. 52:27H-60 et. seq.

“Urban Redevelopment Area” is defined as previously developed portions of areas:

1. Delineated on the State Plan Policy Map (SPPM) as the Metropolitan Planning Area (PA1), Designated Centers, Cores or Nodes;
2. Designated as CAFRA Centers, Cores or Nodes;
3. Designated as Urban Enterprise Zones; and
4. Designated as Urban Coordinating Council Empowerment Neighborhoods.

“Water control structure” means a structure within, or adjacent to, a water, which intentionally or coincidentally alters the hydraulic capacity, the flood elevation resulting from the two-, 10-, or 100-year storm, flood hazard area limit, and/or floodway limit of the water. Examples of a water control structure may include a bridge, culvert, dam, embankment, ford (if above grade), retaining wall, and weir.

“Waters of the State” means the ocean and its estuaries, all springs, streams, wetlands, and bodies of surface or groundwater, whether natural or artificial, within the boundaries of the State of New Jersey or subject to its jurisdiction.

“Wetlands” or “wetland” means an area that is inundated or saturated by surface water or ground water at a frequency and duration sufficient to support, and that under normal circumstances does support, a prevalence of vegetation typically adapted for life in saturated soil conditions, commonly known as hydrophytic vegetation.

§ 224-313. Design and Performance Standards for Stormwater Management Measures

- A. Stormwater management measures for major development shall be designed to provide erosion control, groundwater recharge, stormwater runoff quantity control, and stormwater runoff quality treatment as follows:
 - 1. The minimum standards for erosion control are those established under the Soil and Sediment Control Act, N.J.S.A. 4:24-39 et seq., and implementing rules at N.J.A.C. 2:90.
 - 2. The minimum standards for groundwater recharge, stormwater quality, and stormwater runoff quantity shall be met by incorporating green infrastructure.
- B. The standards in this Article apply only to new major development and are intended to minimize the impact of stormwater runoff on water quality and water quantity in receiving water bodies and maintain groundwater recharge. The standards do not apply to new major development to the extent that alternative design and performance standards are applicable under a regional stormwater management plan or Water Quality Management Plan adopted in accordance with Department rules.

§ 224-314. Stormwater Management Requirements for Major Development

- A. The development shall incorporate a maintenance plan for the stormwater management measures incorporated into the design of a major development in accordance with § 224-310.
- B. Stormwater management measures shall avoid adverse impacts of concentrated flow on habitat for threatened and endangered species as documented in the Department’s Landscape Project or Natural Heritage Database established under N.J.S.A. 13:1B-15.147 through 15.150, particularly *Helonias bullata* (swamp pink) and/or *Clemmys muhlenbergi* (bog turtle).
- C. The following linear development projects are exempt from the groundwater recharge, stormwater runoff quality, and stormwater runoff quantity requirements of § 224-314.P, Q and R:
 - 1. The construction of an underground utility line provided that the disturbed areas are revegetated upon completion;
 - 2. The construction of an aboveground utility line provided that the existing conditions are maintained to the maximum extent practicable; and
 - 3. The construction of a public pedestrian access, such as a sidewalk or trail with a maximum width of 14 feet, provided that the access is made of permeable material.

- D. A waiver from strict compliance from the green infrastructure, groundwater recharge, stormwater runoff quality, and stormwater runoff quantity requirements of § 224-314.O, P, Q and R may be obtained for the enlargement of an existing public roadway or railroad; or the construction or enlargement of a public pedestrian access, provided that the following conditions are met:
1. The applicant demonstrates that there is a public need for the project that cannot be accomplished by any other means;
 2. The applicant demonstrates through an alternatives analysis, that through the use of stormwater management measures, the option selected complies with the requirements of § 224-314.O, P, Q and R to the maximum extent practicable;
 3. The applicant demonstrates that, in order to meet the requirements of § 224-314.O, P, Q and R, existing structures currently in use, such as homes and buildings, would need to be condemned; and
 4. The applicant demonstrates that it does not own or have other rights to areas, including the potential to obtain through condemnation lands not falling under
 5. § 224-314.D.3 above within the upstream drainage area of the receiving stream, that would provide additional opportunities to mitigate the requirements of § 224-314.O, P, Q and R that were not achievable onsite.

- E. Tables 1 through 3 below summarize the ability of stormwater best management practices identified and described in the New Jersey Stormwater Best Management

Practices Manual to satisfy the green infrastructure, groundwater recharge, stormwater runoff quality and stormwater runoff quantity standards specified in § 224-314.O, P, Q and R. When designed in accordance with the most current version of the New Jersey Stormwater Best Management Practices Manual, the stormwater management measures found at N.J.A.C. 7:8-5.2 (f) Tables 5-1, 5-2 and 5-3 and listed below in Tables 1, 2 and 3 are presumed to be capable of providing stormwater controls for the design and performance standards as outlined in the tables below. Upon amendments of the New Jersey Stormwater Best Management Practices to reflect additions or deletions of BMPs meeting these standards, or changes in the presumed performance of BMPs designed in accordance with the New Jersey Stormwater BMP Manual, the Department shall publish in the New Jersey Registers a notice of administrative change revising the applicable table. The most current version of the BMP Manual can be found on the Department's website at:

<https://dep.nj.gov/stormwater/bmp-manual/>.

- F. Where the BMP tables in the NJ Stormwater Management Rule are different due to updates or amendments with the tables in this Article the BMP Tables in the Stormwater Management rule at N.J.A.C. 7:8-5.2(f) shall take precedence.

Table 1 Green Infrastructure BMPs for Groundwater Recharge, Stormwater Runoff Quality, and/or Stormwater Runoff Quantity				
Best Management Practice	Stormwater Runoff Quality TSS Removal Rate (percent)	Stormwater Runoff Quantity	Groundwater Recharge	Minimum Separation from Seasonal High Water Table (feet)
Cistern	0	Yes	No	--
Dry Well ^(a)	0	No	Yes	2
Grass Swale	50 or less	No	No	2 ^(e) 1 ^(f)
Green Roof	0	Yes	No	--

Manufactured Treatment Device ^(a) (g)	50 or 80	No	No	Dependent upon the device
Pervious Paving System ^(a)	80	Yes	Yes ^(b) No ^(c)	2 ^(b) 1 ^(c)
Small-Scale Bioretention Basin ^(a)	80 or 90	Yes	Yes ^(b) No ^(c)	2 ^(b) 1 ^(c)
Small-Scale Infiltration Basin ^(a)	80	Yes	Yes	2
Small-Scale Sand Filter	80	Yes	Yes	2
Vegetative Filter Strip	60-80	No	No	--

Table 2 Green Infrastructure BMPs for Stormwater Runoff Quantity (or for Groundwater Recharge and/or Stormwater Runoff Quality with a Waiver or Variance from N.J.A.C. 7:8-5.3)				
Best Management Practice	Stormwater Runoff Quality TSS Removal Rate (percent)	Stormwater Runoff Quantity	Groundwater Recharge	Minimum Separation from Seasonal High Water Table (feet)
Bioretention System	80 or 90	Yes	Yes ^(b) No ^(c)	2 ^(b) 1 ^(c)
Infiltration Basin	80	Yes	Yes	2
Sand Filter ^(b)	80	Yes	Yes	2
Standard Constructed Wetland	90	Yes	No	N/A
Wet Pond ^(d)	50-90	Yes	No	N/A

Table 3 BMPs for Groundwater Recharge, Stormwater Runoff Quality, and/or Stormwater Runoff Quantity only with a Waiver or Variance from N.J.A.C. 7:8-5.3				
Best Management Practice	Stormwater Runoff Quality TSS Removal Rate (percent)	Stormwater Runoff Quantity	Groundwater Recharge	Minimum Separation from Seasonal High Water Table (feet)
Blue Roof	0	Yes	No	N/A
Extended Detention Basin	40-60	Yes	No	1
Manufactured Treatment Device ^(h)	50 or 80	No	No	Dependent upon the device

Sand Filter ^(c)	80	Yes	No	1
Subsurface Gravel Wetland	90	No	No	1
Wet Pond	50-90	Yes	No	N/A

Notes to Tables 1, 2, and 3:

- (a) subject to the applicable contributory drainage area limitation specified at § 224-314.O.2;
- (b) designed to infiltrate into the subsoil;
- (c) designed with underdrains;
- (d) designed to maintain at least a 10-foot wide area of native vegetation along at least 50 percent of the shoreline and to include a stormwater runoff retention component designed to capture stormwater runoff for beneficial reuse, such as irrigation;
- (e) designed with a slope of less than two percent;
- (f) designed with a slope of equal to or greater than two percent;
- (g) manufactured treatment devices that meet the definition of green infrastructure at § 224-312;
- (h) manufactured treatment devices that do not meet the definition of green infrastructure at § 224-312.

- G. An alternative stormwater management measure, alternative removal rate, and/or alternative method to calculate the removal rate may be used if the design engineer demonstrates the capability of the proposed alternative stormwater management measure and/or the validity of the alternative rate or method to the municipality. A copy of any approved alternative stormwater management measure, alternative removal rate, and/or alternative method to calculate the removal rate shall be provided to the Department in accordance with § 224-314..B. Alternative stormwater management measures may be used to satisfy the requirements at § 224-314.O only if the measures meet the definition of green infrastructure at § 224-312. Alternative stormwater management measures that function in a similar manner to a BMP listed at § 224-4. O.2 are subject to the contributory drainage area limitation specified at § 224-4. O.2 for that similarly functioning BMP. Alternative stormwater management measures approved in accordance with this subsection that do not function in a similar manner to any BMP listed at § 224-314.O.2 shall have a contributory drainage area less than or equal to 2.5 acres, except for alternative stormwater management measures that function similarly to cisterns, grass swales, green roofs, standard constructed wetlands, vegetative filter strips, and wet ponds, which are not subject to a contributory drainage area limitation. Alternative measures that function similarly to standard constructed wetlands or wet ponds shall not be used for compliance with the stormwater runoff quality standard unless a variance in accordance with N.J.A.C. 7:8-4.6 or a waiver from strict compliance in accordance with § 224-314.D is granted from § 224-314.O.
- H. Whenever the stormwater management design includes one or more BMPs that will infiltrate stormwater into subsoil, the design engineer shall assess the hydraulic impact on the groundwater table and design the site, so as to avoid adverse hydraulic impacts. Potential adverse hydraulic impacts include, but are not limited to, exacerbating a naturally or seasonally high-water table, so as to cause surficial ponding, flooding of basements, or interference with the proper operation of subsurface sewage disposal systems or other subsurface structures within the zone of influence of the groundwater mound, or interference with the proper functioning of the stormwater management measure itself.
- I. Design standards for stormwater management measures are as follows:
1. Stormwater management measures shall be designed to take into account the existing site conditions, including, but not limited to, environmentally critical areas; wetlands; flood-prone areas; slopes; depth to seasonal high-water table; soil type, permeability, and texture; drainage area and drainage patterns; and the presence of solution-prone carbonate rocks (limestone);
 2. Stormwater management measures shall be designed to minimize maintenance, facilitate maintenance and repairs, and ensure proper functioning. Trash racks shall be installed at the intake to the outlet structure, as appropriate, and shall have parallel bars with one-inch spacing between the bars to the elevation of the water quality design storm. For elevations higher than the water quality design storm, the parallel bars at the outlet structure shall be spaced no greater than one-third the width of the diameter of the orifice or one-third the width of the weir, with a minimum

- spacing between bars of one inch and a maximum spacing between bars of six inches. In addition, the design of trash racks must comply with the requirements of § 224-318.C;
3. Stormwater management measures shall be designed, constructed, and installed to be strong, durable, and corrosion resistant. Measures that are consistent with the relevant portions of the Residential Site Improvement Standards at N.J.A.C. 5:21-7.3, 7.4, and 7.5 shall be deemed to meet this requirement;
 4. Stormwater management BMPs shall be designed to meet the minimum safety standards for stormwater management BMPs at § 224-318; and
 5. The size of the orifice at the intake to the outlet from the stormwater management BMP shall be a minimum of two and one-half inches in diameter.
- J. Manufactured treatment devices may be used to meet the requirements of this Article, provided the pollutant removal rates are verified by the New Jersey Corporation for Advanced Technology and certified by the Department. Manufactured treatment devices that do not meet the definition of green infrastructure at § 224-2 may be used only under the circumstances described at § 224-314.O.4.
- K. Any application for a new agricultural development that meets the definition of major development at § 224-2 shall be submitted to the Soil Conservation District for review and approval in accordance with the requirements at § 224-314.O, P, Q and R and any applicable Soil Conservation District guidelines for stormwater runoff quantity and erosion control. For purposes of this subsection, "agricultural development" means land uses normally associated with the production of food, fiber, and livestock for sale. Such uses do not include the development of land for the processing or sale of food and the manufacture of agriculturally related products.
- L. If there is more than one drainage area, the groundwater recharge, stormwater runoff quality, and stormwater runoff quantity standards at § 224-314.P, Q and R shall be met in each drainage area, unless the runoff from the drainage areas converge onsite and no adverse environmental impact would occur as a result of compliance with any one or more of the individual standards being determined utilizing a weighted average of the results achieved for that individual standard across the affected drainage areas.
- M. Any stormwater management measure authorized under the municipal stormwater management plan or ordinance shall be reflected in a deed notice recorded in the Office of the Atlantic County Clerk's office. A form of deed notice shall be submitted to the municipality for approval prior to filing. The deed notice shall contain a description of the stormwater management measure(s) used to meet the green infrastructure, groundwater recharge, stormwater runoff quality, and stormwater runoff quantity standards at § 224-314.O, P, Q and R and shall identify the location of the stormwater management measure(s) in NAD 1983 State Plane New Jersey FIPS 2900 US Feet or Latitude and Longitude in decimal degrees. The deed notice shall also reference the maintenance plan required to be recorded upon the deed pursuant to § 224-320.B.5. Prior to the commencement of construction, proof that the above required deed notice has been filed shall be submitted to the municipality. Proof that the required information has been recorded on the deed shall be in the form of either a copy of the complete recorded document or a receipt from the clerk or other proof of recordation provided by the recording office. However, if the initial proof provided to the municipality is not a copy of the complete recorded document, a copy of the complete recorded document shall be provided to the municipality within 180 calendar days of the authorization granted by the municipality.
- N. A stormwater management measure approved under the municipal stormwater management plan or ordinance may be altered or replaced with the approval of the municipality, if the municipality determines that the proposed alteration or replacement meets the design and performance standards pursuant to § 224-314 of this Article and provides the same level of stormwater management as the previously approved stormwater management measure that is being altered or replaced. If an alteration or replacement is approved, a revised deed notice shall be submitted to the municipality for approval and subsequently recorded with the Atlantic County Clerk's office and shall contain a description and location of the stormwater management measure, as well as reference to the maintenance plan, in accordance with M above. Prior to the commencement of construction, proof

that the above required deed notice has been filed shall be submitted to the municipality in accordance with M above.

O. Green Infrastructure Standards

1. This subsection specifies the types of green infrastructure BMPs that may be used to satisfy the groundwater recharge, stormwater runoff quality, and stormwater runoff quantity standards.
2. To satisfy the groundwater recharge and stormwater runoff quality standards at § 224-314.P and Q, the design engineer shall utilize green infrastructure BMPs identified in Table 1 at § 224-314.F. and/or an alternative stormwater management measure approved in accordance with § 224-314.G. The following green infrastructure BMPs are subject to the following maximum contributory drainage area limitations:

Best Management Practice	Maximum Contributory Drainage Area
Dry Well	1 acre
Manufactured Treatment Device	2.5 acres
Pervious Pavement Systems	Area of additional inflow cannot exceed three times the area occupied by the BMP
Small-scale Bioretention Systems	2.5 acres
Small-scale Infiltration Basin	2.5 acres
Small-scale Sand Filter	2.5 acres

3. To satisfy the stormwater runoff quantity standards at § 224-314.R, the design engineer shall utilize BMPs from Table 1 or from Table 2 and/or an alternative stormwater management measure approved in accordance with § 224-314.G.
4. If a variance in accordance with N.J.A.C. 7:8-4.6 or a waiver from strict compliance in accordance with § 224-4.D is granted from the requirements of this subsection, then BMPs from Table 1, 2, or 3, and/or an alternative stormwater management measure approved in accordance with § 224-314.G may be used to meet the groundwater recharge, stormwater runoff quality, and stormwater runoff quantity standards at § 224-314.P, Q and R.
5. For separate or combined storm sewer improvement projects, such as sewer separation, undertaken by a government agency or public utility (for example, a sewerage company), the requirements of this subsection shall only apply to areas owned in fee simple by the government agency or utility, and areas within a right-of-way or easement held or controlled by the government agency or utility; the entity shall not be required to obtain additional property or property rights to fully satisfy the requirements of this subsection. Regardless of the amount of area of a separate or combined storm sewer improvement project subject to the green infrastructure requirements of this subsection, each project shall fully comply with the applicable groundwater recharge, stormwater runoff quality control, and stormwater runoff quantity standards at § 224-314.P, Q and R, unless the project is granted a waiver from strict compliance in accordance with § 224-314.D.

P. Groundwater Recharge Standards

1. This subsection contains the minimum design and performance standards for groundwater recharge as follows:
2. The design engineer shall, using the assumptions and factors for stormwater runoff and groundwater recharge calculations at § 224-315, either:

- i. Demonstrate through hydrologic and hydraulic analysis that the site and its stormwater management measures maintain 100 percent of the average annual pre-construction groundwater recharge volume for the site; or
 - ii. Demonstrate through hydrologic and hydraulic analysis that the increase of stormwater runoff volume from pre-construction to post-construction for the projected 2-year storm, as defined and determined pursuant to § 224-315.D of this Article is infiltrated.
- 3. This groundwater recharge requirement does not apply to projects within the “urban redevelopment area,” or to projects subject to 4 below.
- 4. The following types of stormwater shall not be recharged:
 - i. Stormwater from areas of high pollutant loading. High pollutant loading areas are areas in industrial and commercial developments where solvents and/or petroleum products are loaded/unloaded, stored, or applied, areas where pesticides are loaded/unloaded or stored; areas where hazardous materials are expected to be present in greater than “reportable quantities” as defined by the United States Environmental Protection Agency (EPA) at 40 CFR 302.4; areas where recharge would be inconsistent with Department approved remedial action work plan approved pursuant to the Administrative Requirements for the Remediation of Contaminated Sites rules, N.J.A.C. 7:26C, or Department landfill closure plan and areas; and areas with high risks for spills of toxic materials, such as gas stations and vehicle maintenance facilities; and
 - ii. Industrial stormwater exposed to “source material.” “Source material” means any material(s) or machinery, located at an industrial facility, that is directly or indirectly related to process, manufacturing or other industrial activities, which could be a source of pollutants in any industrial stormwater discharge to groundwater. Source materials include, but are not limited to, raw materials; intermediate products; final products; waste materials; by-products; industrial machinery and fuels, and lubricants, solvents, and detergents that are related to process, manufacturing, or other industrial activities that are exposed to stormwater.

Q. Stormwater Runoff Quality Standards

- 1. This subsection contains the minimum design and performance standards to control stormwater runoff quality impacts of major development. Stormwater runoff quality standards are applicable when the major development results in an increase of one-quarter acre or more of regulated motor vehicle surface.
- 2. Stormwater management measures shall be designed to reduce the post-construction load of total suspended solids (TSS) in stormwater runoff generated from the water quality design storm as follows:
 - i. Eighty percent TSS removal of the anticipated load, expressed as an annual average shall be achieved for the stormwater runoff from the net increase of motor vehicle surface.
 - ii. If the surface is considered regulated motor vehicle surface because the water quality treatment for an area of motor vehicle surface that is currently receiving water quality treatment either by vegetation or soil, by an existing stormwater management measure, or by treatment at a wastewater treatment plant is to be modified or removed, the project shall maintain or increase the existing TSS removal of the anticipated load expressed as an annual average.
- 3. The requirement to reduce TSS does not apply to any stormwater runoff in a discharge regulated under a numeric effluent limitation for TSS imposed under the New Jersey Pollutant Discharge Elimination System (NJPDES) rules, N.J.A.C. 7:14A, or in a discharge specifically exempt under a NJPDES permit from this requirement. Every major development, including any that discharge into a combined sewer system, shall comply with 2 above, unless the major development is itself subject to a NJPDES permit with a numeric effluent limitation for TSS or the NJPDES permit to which the major development is subject exempts the development from a numeric effluent limitation for TSS.

4. The water quality design storm is 1.25 inches of rainfall in two hours. Water quality calculations shall take into account the distribution of rain from the water quality design storm, as reflected in Table 4, below. The calculation of the volume of runoff may take into account the implementation of stormwater management measures.

Table 4 - Water Quality Design Storm Distribution

Time (Minutes)	Cumulative Rainfall (Inches)	Time (Minutes)	Cumulative Rainfall (Inches)	Time (Minutes)	Cumulative Rainfall (Inches)
1	0.00166	41	0.1728	81	1.0906
2	0.00332	42	0.1796	82	1.0972
3	0.00498	43	0.1864	83	1.1038
4	0.00664	44	0.1932	84	1.1104
5	0.00830	45	0.2000	85	1.1170
6	0.00996	46	0.2117	86	1.1236
7	0.01162	47	0.2233	87	1.1302
8	0.01328	48	0.2350	88	1.1368
9	0.01494	49	0.2466	89	1.1434
10	0.01660	50	0.2583	90	1.1500
11	0.01828	51	0.2783	91	1.1550
12	0.01996	52	0.2983	92	1.1600
13	0.02164	53	0.3183	93	1.1650
14	0.02332	54	0.3383	94	1.1700
15	0.02500	55	0.3583	95	1.1750
16	0.03000	56	0.4116	96	1.1800
17	0.03500	57	0.4650	97	1.1850
18	0.04000	58	0.5183	98	1.1900
19	0.04500	59	0.5717	99	1.1950
20	0.05000	60	0.6250	100	1.2000
21	0.05500	61	0.6783	101	1.2050
22	0.06000	62	0.7317	102	1.2100
23	0.06500	63	0.7850	103	1.2150
24	0.07000	64	0.8384	104	1.2200
25	0.07500	65	0.8917	105	1.2250
26	0.08000	66	0.9117	106	1.2267
27	0.08500	67	0.9317	107	1.2284
28	0.09000	68	0.9517	108	1.2300
29	0.09500	69	0.9717	109	1.2317
30	0.10000	70	0.9917	110	1.2334
31	0.10660	71	1.0034	111	1.2351
32	0.11320	72	1.0150	112	1.2367
33	0.11980	73	1.0267	113	1.2384
34	0.12640	74	1.0383	114	1.2400
35	0.13300	75	1.0500	115	1.2417
36	0.13960	76	1.0568	116	1.2434
37	0.14620	77	1.0636	117	1.2450
38	0.15280	78	1.0704	118	1.2467
39	0.15940	79	1.0772	119	1.2483
40	0.16600	80	1.0840	120	1.2500

5. If more than one BMP in series is necessary to achieve the required 80 percent TSS reduction for a site, the applicant shall utilize the following formula to calculate TSS reduction:

$$R = A + B - (A \times B) / 100,$$

Where

R = total TSS Percent Load Removal from application of both BMPs, and

A = the TSS Percent Removal Rate applicable to the first BMP

B = the TSS Percent Removal Rate applicable to the second BMP.

6. Stormwater management measures shall also be designed to reduce, to the maximum extent feasible, the post-construction nutrient load of the anticipated load from the developed site in stormwater runoff generated from the water quality design storm. In achieving reduction of nutrients to the maximum extent feasible, the design of the site shall include green infrastructure BMPs that optimize nutrient removal while still achieving the performance standards in § 224-314.P, Q and R.
7. In accordance with the definition of FW1 at N.J.A.C. 7:9B-1.4, stormwater management measures shall be designed to prevent any increase in stormwater runoff to waters classified as FW1.
8. The Flood Hazard Area Control Act Rules at N.J.A.C. 7:13-4.1(c)1 establish 300-foot riparian zones along Category One waters, as designated in the Surface Water Quality Standards at N.J.A.C. 7:9B, and certain upstream tributaries to Category One waters. A person shall not undertake a major development that is located within or discharges into a 300-foot riparian zone without prior authorization from the Department under N.J.A.C. 7:13.
9. Pursuant to the Flood Hazard Area Control Act Rules at N.J.A.C. 7:13-11.2(j)3.i, runoff from the water quality design storm that is discharged within a 300-foot riparian zone shall be treated in accordance with this subsection to reduce the post-construction load of total suspended solids by 95 percent of the anticipated load from the developed site, expressed as an annual average.
10. The stormwater runoff quality standards do not apply to the construction of one individual single-family dwelling, provided that it is not part of a larger development or subdivision that has received preliminary or final site plan approval prior to December 3, 2018, and that the motor vehicle surfaces are made of permeable material(s) such as gravel, dirt, and/or shells.

R. Stormwater Runoff Quantity Standards

1. This subsection contains the minimum design and performance standards to control stormwater runoff quantity impacts of major development.
2. In order to control stormwater runoff quantity impacts, the design engineer shall, using the assumptions and factors for stormwater runoff calculations at § 224-315, complete one of the following:
 - i. Demonstrate through hydrologic and hydraulic analysis that for stormwater leaving the site, post-construction runoff hydrographs for the current and projected 2-, 10-, and 100-year storm events, as defined and determined in § 224-315.C and D, respectively, of this Article, do not exceed, at any point in time, the pre-construction runoff hydrographs for the same storm events;
 - ii. Demonstrate through hydrologic and hydraulic analysis that there is no increase, as compared to the pre-construction condition, in the peak runoff rates of stormwater leaving the site for the current and projected 2-, 10-, and 100-year storm events, as defined and determined pursuant to § 224-315.C and D, respectively, of this Article, and that the increased volume or change in timing of stormwater runoff will not increase flood damage at or downstream of the site. This analysis shall include the analysis of impacts of existing land uses and projected land uses assuming full development under existing zoning and land use ordinances in the drainage area;
 - iii. Design stormwater management measures so that the post-construction peak runoff rates for the current and projected 2-, 10-, and 100-year storm events, as defined and determined in § 224-314.C and D, respectively, of this Article, are 50, 75 and 80 percent, respectively, of the pre-construction peak runoff rates. The percentages apply only to the post-construction stormwater runoff that is attributable to the portion of the site on which the proposed development or project is to be constructed; or
 - iv. In tidal flood hazard areas, stormwater runoff quantity analysis in accordance with 2.i, ii and iii above is required unless the design engineer demonstrates through hydrologic and hydraulic

analysis that the increased volume, change in timing, or increased rate of the stormwater runoff, or any combination of the three will not result in additional flood damage below the point of discharge of the major development. No analysis is required if the stormwater is discharged directly into any ocean, bay, inlet, or the reach of any watercourse between its confluence with an ocean, bay, or inlet and downstream of the first water control structure.

3. The stormwater runoff quantity standards shall be applied at the site's boundary to each abutting lot, roadway, watercourse, or receiving storm sewer system.

§ 224-315. Calculation of Stormwater Runoff and Groundwater Recharge:

- A. Stormwater runoff shall be calculated in accordance with the following:

1. The design engineer shall calculate runoff using the following method:

The USDA Natural Resources Conservation Service (NRCS) methodology, including the NRCS Runoff Equation and Dimensionless Unit Hydrograph, as described in Articles 7, 9, 10, 15 and 16 *Part 630, Hydrology National Engineering Handbook*, incorporated herein by reference as amended and supplemented. This methodology is additionally described in *Technical Release 55 - Urban Hydrology for Small Watersheds* (TR-55), dated June 1986, incorporated herein by reference as amended and supplemented. Information regarding the methodology is available from the Natural Resources Conservation Service website at:

<https://directives.sc.egov.usda.gov/viewerFS.aspx?hid=21422>

or at United States Department of Agriculture Natural Resources Conservation Service, New Jersey State Office.

2. For the purpose of calculating curve numbers and groundwater recharge, there is a presumption that the pre-construction condition of a site or portion thereof is a wooded land use with good hydrologic condition. The term "curve number" applies to the NRCS methodology above at § 224-315.A.1. A curve number or a groundwater recharge land cover for an existing condition may be used on all or a portion of the site if the design engineer verifies that the hydrologic condition has existed on the site or portion of the site for at least five years without interruption prior to the time of application. If more than one land cover has existed on the site during the five years immediately prior to the time of application, the land cover with the lowest runoff potential shall be used for the computations. In addition, there is the presumption that the site is in good hydrologic condition (if the land use type is pasture, lawn, or park), with good cover (if the land use type is woods), or with good hydrologic condition and conservation treatment (if the land use type is cultivation).
3. In computing pre-construction stormwater runoff, the design engineer shall account for all significant land features and structures, such as ponds, wetlands, depressions, hedgerows, or culverts, that may reduce pre-construction stormwater runoff rates and volumes.
4. In computing stormwater runoff from all design storms, the design engineer shall consider the relative stormwater runoff rates and/or volumes of pervious and impervious surfaces separately to accurately compute the rates and volume of stormwater runoff from the site. To calculate runoff from unconnected impervious cover, urban impervious area modifications as described in the NRCS *Technical Release 55 – Urban Hydrology for Small Watersheds* or other methods may be employed.
5. If the invert of the outlet structure of a stormwater management measure is below the flood hazard design flood elevation as defined at N.J.A.C. 7:13, the design engineer shall take into account the effects of tailwater in the design of structural stormwater management measures.

- B. Groundwater recharge may be calculated in accordance with the following:

The New Jersey Geological Survey Report GSR-32: A Method for Evaluating Groundwater-Recharge Areas in New Jersey, incorporated herein by reference as amended and supplemented. Information regarding the methodology is available from the New Jersey Stormwater Best Management Practices Manual; at the New Jersey Geological Survey website at:

<https://www.nj.gov/dep/njgs/pricelst/gsreport/gsr32.pdf>

or at New Jersey Geological and Water Survey, 29 Arctic Parkway, PO Box 420 Mail Code 29-01, Trenton, New Jersey 08625-0420.

- C. The precipitation depths of the current two-, 10-, and 100-year storm events shall be determined by multiplying the values determined in accordance with items 1 and 2 below:

1. The applicant shall utilize the National Oceanographic and Atmospheric Administration (NOAA), National Weather Service's Atlas 14 Point Precipitation Frequency Estimates: NJ, in accordance with the location(s) of the drainage area(s) of the site. This data is available at:

https://hdsc.nws.noaa.gov/hdsc/pfds/pfds_map_cont.html?bkmrk=nj; and

2. The applicant shall utilize Table 5: Current Precipitation Adjustment Factors below, which sets forth the applicable multiplier for the drainage area(s) of the site, in accordance with the county or counties where the drainage area(s) of the site is located. Where the major development lies in more than one county, the precipitation values shall be adjusted according to the percentage of the drainage area in each county. Alternately, separate rainfall totals can be developed for each county using the values in the table below.

Table 5: Current Precipitation Adjustment Factors

County	Current Precipitation Adjustment Factors		
	2-year Design Storm	10-year Design Storm	100-year Design Storm
Atlantic	1.01	1.02	1.03

- D. Table 6: Future Precipitation Change Factors provided below sets forth the change factors to be used in determining the projected two-, 10-, and 100-year storm events for use in this Article, which are organized alphabetically by county. The precipitation depth of the projected two-, 10-, and 100-year storm events of a site shall be determined by multiplying the precipitation depth of the two-, 10-, and 100-year storm events determined from the National Weather Service's Atlas 14 Point Precipitation Frequency Estimates pursuant to (c)1 above, by the change factor in the table below, in accordance with the county or counties where the drainage area(s) of the site is located. Where the major development and/or its drainage area lies in more than one county, the precipitation values shall be adjusted according to the percentage of the drainage area in each county. Alternately, separate rainfall totals can be developed for each county using the values in the table below.

Table 6: Future Precipitation Change Factors

County	Future Precipitation Change Factors		
	2-year Design Storm	10-year Design Storm	100-year Design Storm
Atlantic	1.22	1.24	1.39

§ 224-316. Sources for Technical Guidance:

- A. Technical guidance for stormwater management measures can be found in the documents listed below, which are available to download from the Department's website at:

<https://dep.nj.gov/stormwater/bmp-manual/>.

1. Guidelines for stormwater management measures are contained in the New Jersey Stormwater Best Management Practices Manual, as amended and supplemented. Information is provided on stormwater management measures such as, but not limited to, those listed in Tables 1, 2, and 3.
2. Additional maintenance guidance is available on the Department's website at:

<https://dep.nj.gov/stormwater/maintenance-guidance/>.

- B. Submissions required for review by the Department should be mailed to:

The Division of Watershed Protection and Restoration, New Jersey Department of Environmental Protection, Mail Code 501-02A, PO Box 420, Trenton, New Jersey 08625-0420.

§ 224-317. Solids and Floatable Materials Control Standards:

- A. Site design features identified under § 224-314.F above, or alternative designs in accordance with § 224-314.G above, to prevent discharge of trash and debris from drainage systems shall comply with the following standard to control passage of solid and floatable materials through storm drain inlets. For purposes of this paragraph, "solid and floatable materials" means sediment, debris, trash, and other floating, suspended, or settleable solids. For exemptions to this standard see § 224-317.A.2 below.

1. Design engineers shall use one of the following grates whenever they use a grate in pavement or another ground surface to collect stormwater from that surface into a storm drain or surface water body under that grate:
 - i. The New Jersey Department of Transportation (NJDOT) bicycle safe grate, which is described in Article 2.4 of the NJDOT Bicycle Compatible Roadways and Bikeways Planning and Design Guidelines; or
 - ii. A different grate, if each individual clear space in that grate has an area of no more than seven (7.0) square inches, or is no greater than 0.5 inches across the smallest dimension.

Examples of grates subject to this standard include grates in grate inlets, the grate portion (non-curb-opening portion) of combination inlets, grates on storm sewer manholes, ditch grates, trench grates, and grates of spacer bars in slotted drains. Examples of ground surfaces include surfaces of roads (including bridges), driveways, parking areas, bikeways, plazas, sidewalks, lawns, fields, open channels, and stormwater system floors used to collect stormwater from the surface into a storm drain or surface water body.

- iii. For curb-opening inlets, including curb-opening inlets in combination inlets, the clear space in that curb opening, or each individual clear space if the curb opening has two or more clear spaces, shall have an area of no more than seven (7.0) square inches, or be no greater than two (2.0) inches across the smallest dimension.
2. The standard in A.1. above does not apply:
 - i. Where each individual clear space in the curb opening in existing curb-opening inlet does not have an area of more than nine (9.0) square inches;
 - ii. Where the municipality agrees that the standards would cause inadequate hydraulic performance that could not practicably be overcome by using additional or larger storm drain inlets;

- iii. Where flows from the water quality design storm as specified in N.J.A.C. 7:8 are conveyed through any device (e.g., end of pipe netting facility, manufactured treatment device, or a catch basin hood) that is designed, at a minimum, to prevent delivery of all solid and floatable materials that could not pass through one of the following:
 - a. A rectangular space four and five-eighths (4.625) inches long and one and one-half (1.5) inches wide (this option does not apply for outfall netting facilities); or
 - b. A bar screen having a bar spacing of 0.5 inches.

Note that these exemptions do not authorize any infringement of requirements in the Residential Site Improvement Standards for bicycle safe grates in new residential development (N.J.A.C. 5:21-4.18(b)2 and 7.4(b)1).

- iv. Where flows are conveyed through a trash rack that has parallel bars with one-inch (1 inch) spacing between the bars, to the elevation of the Water Quality Design Storm as specified in N.J.A.C. 7:8; or
- v. Where the New Jersey Department of Environmental Protection determines, pursuant to the New Jersey Register of Historic Places Rules at N.J.A.C. 7:4-7.2(c), that action to meet this standard is an undertaking that constitutes an encroachment or will damage or destroy the New Jersey Register listed historic property.

§ 224-318. Safety Standards for Stormwater Management Basins:

- A. This section sets forth requirements to protect public safety through the proper design and operation of stormwater management BMPs. This section applies to any new stormwater management BMP.
- B. The provisions of this section are not intended to preempt more stringent municipal or county safety requirements for new or existing stormwater management BMPs. Municipal and county stormwater management plans and ordinances may, pursuant to their authority, require existing stormwater management BMPs to be retrofitted to meet one or more of the safety standards in § 224-318.C.1, § 224-318.C.2, and § 224-318.C.3 for trash racks, overflow grates, and escape provisions at outlet structures.
- C. Requirements for Trash Racks, Overflow Grates and Escape Provisions
 - 1. A trash rack is a device designed to catch trash and debris and prevent the clogging of outlet structures. Trash racks shall be installed at the intake to the outlet from the Stormwater management BMP to ensure proper functioning of the BMP outlets in accordance with the following:
 - i. The trash rack shall have parallel bars, with no greater than six-inch spacing between the bars;
 - ii. The trash rack shall be designed so as not to adversely affect the hydraulic performance of the outlet pipe or structure;
 - iii. The average velocity of flow through a clean trash rack is not to exceed 2.5 feet per second under the full range of stage and discharge. Velocity is to be computed on the basis of the net area of opening through the rack; and
 - iv. The trash rack shall be constructed of rigid, durable, and corrosion resistant material and designed to withstand a perpendicular live loading of 300 pounds per square foot.
 - 2. An overflow grate is designed to prevent obstruction of the overflow structure. If an outlet structure has an overflow grate, such grate shall meet the following requirements:
 - i. The overflow grate shall be secured to the outlet structure but removable for emergencies and maintenance.
 - ii. The overflow grate spacing shall be no greater than two inches across the smallest dimension


- iii. The overflow grate shall be constructed and installed to be rigid, durable, and corrosion resistant, and shall be designed to withstand a perpendicular live loading of 300 pounds per square foot.
3. Stormwater management BMPs shall include escape provisions as follows:
- i. If a stormwater management BMP has an outlet structure, escape provisions shall be incorporated in or on the structure. Escape provisions include the installation of permanent ladders, steps, rungs, or other features that provide easily accessible means of egress from stormwater management BMPs. With the prior approval of the municipality pursuant to § 224-318.C, a free-standing outlet structure may be exempted from this requirement;
 - ii. Safety ledges shall be constructed on the slopes of all new stormwater management BMPs having a permanent pool of water deeper than two and one-half feet. Safety ledges shall be comprised of two steps. Each step shall be four to six feet in width. One step shall be located approximately two and one-half feet below the permanent water surface, and the second step shall be located one to one and one-half feet above the permanent water surface. See VIII.E for an illustration of safety ledges in a stormwater management BMP; and
 - iii. In new stormwater management BMPs, the maximum interior slope for an earthen dam, embankment, or berm shall not be steeper than three horizontals to one vertical.

D. Variance or Exemption from Safety Standard

A variance or exemption from the safety standards for stormwater management BMPs may be granted only upon a written finding by the municipality that the variance or exemption will not constitute a threat to public safety.

E. Safety Ledge Illustration

Elevation View –Basin Safety Ledge Configuration



§ 224-199. Requirements for a Site Development Stormwater Plan:

A. Submission of Site Development Stormwater Plan

1. Whenever an applicant seeks municipal approval of a development subject to this Article, the applicant shall submit all of the required components of the Checklist for the Site Development Stormwater Plan at § 224-319.C below as part of the submission of the application for approval.
2. The applicant shall demonstrate that the project meets the standards set forth in this Article.

3. The applicant shall submit three copies of the materials listed in the checklist for site development stormwater plans in accordance with § 224-319.C of this Article

B. Site Development Stormwater Plan Approval

The applicant's Site Development project shall be reviewed as a part of the review process by the municipal board or official from which municipal approval is sought. That municipal board or official shall consult the municipality's review engineer to determine if all of the checklist requirements have been satisfied and to determine if the project meets the standards set forth in this Article.

C. Submission of Site Development Stormwater Plan

The following information shall be required:

1. Topographic Base Map

The reviewing engineer may require upstream tributary drainage system information as necessary. It is recommended that the topographic base map of the site be submitted which extends a minimum of 200 feet beyond the limits of the proposed development, at a scale of 1"=200' or greater, showing 2-foot contour intervals. The map as appropriate may indicate the following: existing surface water drainage, shorelines, steep slopes, soils, erodible soils, perennial or intermittent streams that drain into or upstream of the Category One waters, wetlands and flood plains along with their appropriate buffer strips, marshlands and other wetlands, pervious or vegetative surfaces, existing man-made structures, roads, bearing and distances of property lines, and significant natural and manmade features not otherwise shown.

2. Environmental Site Analysis

A written and graphic description of the natural and man-made features of the site and its surroundings should be submitted. This description should include a discussion of soil conditions, slopes, wetlands, waterways and vegetation on the site. Particular attention should be given to unique, unusual, or environmentally sensitive features and to those that provide particular opportunities or constraints for development.

3. Project Description and Site Plans

A map (or maps) at the scale of the topographical base map indicating the location of existing and proposed buildings roads, parking areas, utilities, structural facilities for stormwater management and sediment control, and other permanent structures. The map(s) shall also clearly show areas where alterations will occur in the natural terrain and cover, including lawns and other landscaping, and seasonal high groundwater elevations. A written description of the site plan and justification for proposed changes in natural conditions shall also be provided.

4. Land Use Planning and Source Control Plan

This plan shall provide a demonstration of how the goals and standards of § 224-4.III through V are being met. The focus of this plan shall be to describe how the site is being developed to meet the objective of controlling groundwater recharge, stormwater quality and stormwater quantity problems at the source by land management and source controls whenever possible.

5. Stormwater Management Facilities Map

The following information, illustrated on a map of the same scale as the topographic base map, shall be included:

- i. Total area to be disturbed, paved or built upon, proposed surface contours, land area to be occupied by the stormwater management facilities and the type of vegetation thereon, and details of the proposed plan to control and dispose of stormwater.
- ii. Details of all stormwater management facility designs, during and after construction, including discharge provisions, discharge capacity for each outlet at different levels of detention and emergency spillway provisions with maximum discharge capacity of each spillway.

6. Calculations

- i. Comprehensive hydrologic and hydraulic design calculations for the pre-development and post-development conditions for the design storms specified in § 224-314 of this Article.
- ii. When the proposed stormwater management control measures depend on the hydrologic properties of soils or require certain separation from the seasonal high water table, then a soils report shall be submitted. The soils report shall be based on onsite boring logs or soil pit profiles. The number and location of required soil borings or soil pits shall be determined based on what is needed to determine the suitability and distribution of soils present at the location of the control measure.

7. Maintenance and Repair Plan

The design and planning of the stormwater management facility shall meet the maintenance requirements of § 224-320.

8. Waiver from Submission Requirements

The municipal official or board reviewing an application under this Article may, in consultation with the municipality's review engineer, waive submission of any of the requirements in § 224-319.C.1 through § 224-319.C.6 of this Article when it can be demonstrated that the information requested is impossible to obtain or it would create a hardship on the applicant to obtain and its absence will not materially affect the review process.

§ 224-320. Maintenance and Repair:

A. Applicability

Projects subject to review as in § 224-311.C of this Article shall comply with the requirements of § 224-320.B and § 224-319.C.

B. General Maintenance

1. The design engineer shall prepare a maintenance plan for the stormwater management measures incorporated into the design of a major development.
2. The maintenance plan shall contain specific preventative maintenance tasks and schedules; cost estimates, including estimated cost of sediment, debris, or trash removal; and the name, address, and telephone number of the person or persons responsible for preventative and corrective maintenance (including replacement). The plan shall contain information on BMP location, design, ownership, maintenance tasks and frequencies, and other details as specified in Article 8 of the NJ BMP Manual, as well as the tasks specific to the type of BMP, as described in the applicable Article containing design specifics.
3. If the maintenance plan identifies a person other than the property owner (for example, a developer, a public agency or homeowners' association) as having the responsibility for maintenance, the plan shall include documentation of such person's or entity's agreement to assume this responsibility, or of the owner's obligation to dedicate a stormwater management facility to such person under an applicable ordinance or regulation.

4. Responsibility for maintenance shall not be assigned or transferred to the owner or tenant of an individual property in a residential development or project, unless such owner or tenant owns or leases the entire residential development or project. The individual property owner may be assigned incidental tasks, such as weeding of a green infrastructure BMP, provided the individual agrees to assume these tasks; however, the individual cannot be legally responsible for all of the maintenance required.
 5. If the party responsible for maintenance identified under § 224-10.B.3 above is not a public agency, the maintenance plan and any future revisions based on § 224-10.B.7 below shall be recorded upon the deed of record for each property on which the maintenance described in the maintenance plan must be undertaken.
 6. Preventative and corrective maintenance shall be performed to maintain the functional parameters (storage volume, infiltration rates, inflow/outflow capacity, etc.) of the stormwater management measure, including, but not limited to, repairs or replacement to the structure; removal of sediment, debris, or trash; restoration of eroded areas; snow and ice removal; fence repair or replacement; restoration of vegetation; and repair or replacement of non-vegetated linings.
 7. The party responsible for maintenance identified under § 224-320.B.3 above shall perform all of the following requirements:
 - i. maintain a detailed log of all preventative and corrective maintenance for the structural stormwater management measures incorporated into the design of the development, including a record of all inspections and copies of all maintenance-related work orders;
 - ii. evaluate the effectiveness of the maintenance plan at least once per year and adjust the plan and the deed as needed; and
 - iii. retain and make available, upon request by any public entity with administrative, health, environmental, or safety authority over the site, the maintenance plan and the documentation required by § 224-320.B.6 and B.7 above.
 8. The requirements of § 224-320.B.3 and B.4 do not apply to stormwater management facilities that are dedicated to and accepted by the municipality or another governmental agency, subject to all applicable municipal stormwater general permit conditions, as issued by the Department.
 9. In the event that the stormwater management facility becomes a danger to public safety or public health, or if it is in need of maintenance or repair, the municipality shall so notify the responsible person in writing. Upon receipt of that notice, the responsible person shall have fourteen (14) days to effect maintenance and repair of the facility in a manner that is approved by the municipal engineer or his designee. The municipality, in its discretion, may extend the time allowed for effecting maintenance and repair for good cause. If the responsible person fails or refuses to perform such maintenance and repair, the municipality or County may immediately proceed to do so and shall bill the cost thereof to the responsible person. Nonpayment of such bill may result in a lien on the property.
- C. Nothing in this subsection shall preclude the municipality in which the major development is located from requiring the posting of a performance or maintenance guarantee in accordance with N.J.S.A. 40:55D-53

§ 224-321. Penalties:

Any person(s) who erects, constructs, alters, repairs, converts, maintains, or uses any building, structure or land in violation of this Article or found to be in violation of the provisions of this Article shall be subject to the following penalties: a fine not to exceed \$500. Each day that a violation shall continue shall constitute a separate violation.

§ 224-12. Severability:

If the provisions of any section, subsection, paragraph subdivision, or clause of this Article shall be judged invalid by a court of competent jurisdiction, such order of judgement shall not invalidate the remainder of any section, paragraph, subdivision, or clause of this Article.

§ 224-13. When Effective:

This Article shall take effect upon its final passage and publication as required by law.

Dated:

APPROVED: _____
Kimberly Horton, Mayor

ATTEST: _____
Carie A. Crone, RMC, Municipal Clerk

CITY OF ABSECON

ORDINANCE 02-2024

**AN ORDINANCE AMENDING THE CODE OF THE CITY OF ABSECON
CREATING CHAPTER 259 PRIVATELY-OWNED SALT STORAGE**

NOW THEREFOR BE IT ORDAINED by the Council of the City of Absecon, County of Atlantic and State of New Jersey as follows:

§ 259-1. Purpose:

The purpose of this chapter is to prevent stored salt and other solid de-icing materials from being exposed to stormwater.

This chapter establishes requirements for the storage of salt and other solid de-icing materials on properties not owned or operated by the municipality (privately-owned), including residences, in the City of Absecon to protect the environment, public health, safety and welfare, and to prescribe penalties for failure to comply.

§ 259-2 Definitions:

For the purpose of this chapter, the following terms, phrases, words and their derivations shall have the meanings stated herein unless their use in the text of this Chapter clearly demonstrates a different meaning. When consistent with the context, words used in the present tense include the future, words used in the plural number include the singular number, and words used in the singular number include the plural number. The word "shall" is always mandatory and not merely directory.

- A. "De-icing materials" means any granular or solid material such as melting salt or any other granular solid that assists in the melting of snow.
- B. "Impervious surface" means a surface that has been covered with a layer of material so that it is highly resistant to infiltration by water.
- C. "Storm drain inlet" means the point of entry into the storm sewer system.
- D. "Permanent structure" means a permanent building or permanent structure that is anchored to a permanent foundation with an impermeable floor, and that is completely roofed and walled (new structures require a door or other means of sealing the access way from wind driven rainfall).

A fabric frame structure is a permanent structure if it meets the following specifications:

1. Concrete blocks, jersey barriers or other similar material shall be placed around the interior of the structure to protect the side walls during loading and unloading of de-icing materials;

2. The design shall prevent stormwater run-on and run through, and the fabric cannot leak;
 3. The structure shall be erected on an impermeable slab;
 4. The structure cannot be open sided; and
 5. The structure shall have a roll up door or other means of sealing the access way from wind driven rainfall.
- E. "Person" means any individual, corporation, company, partnership, firm, association, or political subdivision of this State subject to municipal jurisdiction.
- F. "Resident" means a person who resides on a residential property where de-icing material is stored.

§ 259-3. Deicing Material Storage Requirements:

- A. Temporary outdoor storage of de-icing materials in accordance with the requirements below is allowed between October 15th and April 15th:
1. Loose materials shall be placed on a flat, impervious surface in a manner that prevents stormwater run-through;
 2. Loose materials shall be placed at least 50 feet from surface water bodies, storm drain inlets, ditches and/or other stormwater conveyance channels;
 3. Loose materials shall be maintained in a cone-shaped storage pile. If loading or unloading activities alter the cone-shape during daily activities, tracked materials shall be swept back into the storage pile, and the storage pile shall be reshaped into a cone after use;
 4. Loose materials shall be covered as follows:
 - a. The cover shall be waterproof, impermeable, and flexible;
 - b. The cover shall extend to the base of the pile(s);
 - c. The cover shall be free from holes or tears;
 - d. The cover shall be secured and weighed down around the perimeter to prevent removal by wind; and
 - e. Weight shall be placed on the cover(s) in such a way that minimizes the potential of exposure as materials shift and runoff flows down to the base of the pile.

- (1) Sandbags lashed together with rope or cable and placed uniformly over the flexible cover, or poly-cord nets provide a suitable method. Items that can potentially hold water (e.g., old tires) shall not be used;
 5. Containers must be sealed when not in use; and
 6. The site shall be free of all de-icing materials between April 16th and October 14th.
- B. De-icing materials should be stored in a permanent structure if a suitable storage structure is available. For storage of loose de-icing materials in a permanent structure, such storage may be permanent, and thus not restricted to October 15 -April 15.
- C. All such temporary and/or permanent structures must also comply with all other local ordinances, including building and zoning regulations.
- D. The property owner, or owner of the de-icing materials if different, shall designate a person(s) responsible for operations at the site where these materials are stored outdoors, and who shall document that weekly inspections are conducted to ensure that the conditions of this ordinance are met. Inspection records shall be kept on site and made available to the municipality upon request.
1. Residents who operate businesses from their homes that utilize de-icing materials are required to perform weekly inspections.

§ 259-4. Exemptions:

Residents may store de-icing materials outside in a solid-walled, closed container that prevents precipitation from entering and exiting the container, and which prevents the de-icing materials from leaking or spilling out. Under these circumstances, weekly inspections are not necessary, but repair or replacement of damaged or inadequate containers shall occur within 2 weeks.

If containerized (in bags or buckets) de-icing materials are stored within a permanent structure, they are not subject to the storage and inspection requirements in § 259-3 above. Piles of de-icing materials are not exempt, even if stored in a permanent structure.

This chapter does not apply to facilities where the stormwater discharges from de-icing material storage activities are regulated under another NJPDES permit.

§ 259-5. Enforcement:

This chapter shall be enforced by the Municipal Officials of the City of Absecon during the course of ordinary enforcement duties.

§ 259-6. Violations and Penalties:

Any person(s) who is found to be in violation of the provisions of this chapter shall have 72 hours to complete corrective action. Repeat violations and/or failure to complete corrective action shall result in fines as follows: a fine not to exceed \$100 per day.

§ 259-7. Severability:

Each section, subsection, sentence, clause, and phrase of this Chapter is declared to be an independent section, subsection, sentence, clause, and phrase, and finding or holding of any such portion of this Ordinance to be unconstitutional, void, or ineffective for any cause or reason shall not affect any other portion of this Ordinance.

§ 259-8. When Effective:

This chapter shall take effect upon its final passage and publication as required by law.

Dated:

APPROVED: _____
Kimberly Horton, Mayor

ATTEST: _____
Carie A. Crone, RMC, Municipal Clerk

CITY OF ABSECON

ORDINANCE 03-2024

**AN ORDINANCE AMENDING THE CODE OF THE CITY OF ABSECON,
CHAPTER 3 – ADMINISTRATIVE CODE, ARTICLE I – MAYOR AND COUNCIL,
§3-11, COUNCIL COMMITTEES**

**NOW THEREFORE, BE IT ORDAINED BY THE MUNICIPAL COUNCIL OF THE CITY
OF ABSECON CITY, NEW JERSEY** that Chapter 3, Article I, §3-11, Council Committees
is hereby amended as follows:

3. Public works, Sewer and Code Enforcement.

(a) The Committee shall have legislative oversight responsibilities
for any and all matters relating to the activities and operation of
the Public Works Department, including but not limited to the
repair and maintenance of public buildings and grounds, streets
and roads, parks and playgrounds and water and sewer
facilities; and all matters relating to the sanitary sewer needs of
the municipality, including seeking out funding sources and
grants. The Committee shall also have legislative oversight for
any and all matters relating to Code Enforcement.

All other terms and conditions of §3-11 remain unchanged.

DATED:

SIGNED: _____
Kimberly Horton, Mayor

ATTEST: _____
Carie A. Crone, RMC, Municipal Clerk

CITY OF ABSECON

RESOLUTION 29-2024

**A RESOLUTION APPOINTING A PUBLIC WORKS
LABORER/OPERATOR**

WHEREAS, there is a need to fill a vacancy for a Full-Time Laborer/Operator in the Public Works Department of the City of Absecon; and

WHEREAS, interviews have been conducted and the person named below has indicated a willingness to serve as a Full-Time Laborer/Operator for the City of Absecon.

NOW THEREFORE BE IT RESOLVED by the Council of the City of Absecon that an appointment be made as follows:

Thomas Andrews - Full-time Laborer/Operator at \$56,355.69 per year,
effective January 22nd, 2024.

Dated: January 18th, 2024

**This is to certify that this is a true
Copy of a Resolution adopted by the
Council of the City of Absecon at a
regular meeting held January 18th, 2024.**

**ATTEST: _____
Carie A. Crone, RMC, Municipal Clerk**

CITY OF ABSECON

RESOLUTION 30-2024

**A RESOLUTION OF THE CITY OF ABSECON PERMITTING A
CHARITABLE ORGANIZATION TO SOLICIT FUNDS, NAMELY
THE ABSECON VFW POST 9462 AUXILIARY**

WHEREAS, the above-mentioned charitable organization meets the definition as defined by N.J.S.A.45: 17A-20 and has made application for a permit to solicit funds on roadways situated in the City of Absecon on Saturday, May 4th, 2024 between the hours of 8:00 am and 2:00 pm (Rain Date, Sunday, May 5th, 2024), has met the requirements as specified in the City of Absecon Ordinance 8 of 1998; and

WHEREAS, the application as filed with the Municipal Clerk by the organization, Absecon VFW Post 9462 Auxiliary has been reviewed and the information on it found satisfactory by the Absecon Police Department.

NOW THEREFORE, BE IT RESOLVED by the Council of the City of Absecon as follows:

1. Permission is granted based upon conditions set forth in the applicant's application for the Absecon VFW Post 9462 Auxiliary to conduct a coin drop on Saturday, May 4th, 2024, (Rain Date, Sunday, May 5th, 2024) between the hours of 8:00 am and 2:00 pm at the intersection of Mill Road and New Jersey Avenue in the City of Absecon.

Dated: January 18th, 2024

**This is to certify that this is a true
Copy of a Resolution adopted by the
Council of the City of Absecon at a
regular meeting held January 18th, 2024**

**ATTEST: _____
Carie A. Crone, RMC, Municipal Clerk**

CITY OF ABSECON

RESOLUTION 31-2024

**A RESOLUTION OF THE CITY OF ABSECON PERMITTING A
CHARITABLE ORGANIZATION TO SOLICIT FUNDS, NAMELY
THE CHARLES A. HAMMEL POST 28 AMERICAN LEGION**

WHEREAS, the above-mentioned charitable organization meets the definition as defined by N.J.S.A.45: 17A-20 and has made application for a permit to solicit funds on roadways situated in the City of Absecon on Saturday, June 7th, and Sunday, June 8th, 2024 between the hours of 9:00 am and 3:00 pm (Rain Dates June 14th and June 15th), has met the requirements as specified in the City of Absecon Ordinance 8 of 1998; and

WHEREAS, the application as filed with the Municipal Clerk by the organization, Charles A. Hammell Post 28 American Legion has been reviewed and the information on it found satisfactory by the Absecon Police Department.

NOW THEREFORE, BE IT RESOLVED by the Council of the City of Absecon as follows:

1. Permission is granted based upon conditions set forth in the applicant's application for the Charles A. Hammell Post 28 American Legion to conduct a coin drop on Saturday, June 7th, and Sunday, June 8th, 2024, (Rain Dates, June 10th and June 11th) between the hours of 9:00 am and 3:00 pm at the intersection of Mill Road and New Jersey Avenue in the City of Absecon.

Dated: January 18th, 2024

**This is to certify that this is a true
copy of a Resolution adopted by the
Council of the City of Absecon at a
Regular Meeting held January 18th, 2024.**

**ATTEST: _____
Carie A. Crone, RMC, Municipal Clerk**

CITY OF ABSECON

RESOLUTION 32-2024

**A RESOLUTION OF THE CITY OF ABSECON PERMITTING
A CHARITABLE ORGANIZATION TO SOLICIT FUNDS,
NAMELY THE ABSECON GREEN TEAM**

WHEREAS, the above-mentioned charitable organization meets the definition as defined by N.J.S.A.45: 17A-20 and has made application for a permit to solicit funds on roadways situated in the City of Absecon on Saturday, February 10th, 2024 between the hours of 10:00 am and 2:00 pm, has met the requirements as specified in the City of Absecon Ordinance 8 of 1998; and

WHEREAS, the application as filed with the Municipal Clerk by the organization, Absecon Green Team has been reviewed and the information on it found satisfactory by the Absecon Police Department.

NOW THEREFORE, BE IT RESOLVED by the Council of the City of Absecon as follows:

1. Permission is granted based upon conditions set forth in the applicant's application for the Absecon Green Team to conduct a coin drop on Saturday, February 10th, 2024, between the hours of 10:00 am and 2:00 pm at the intersection of Mill Road and New Jersey Avenue in the City of Absecon.

Dated: January 18th, 2024

**This is to certify that this is a true
copy of a Resolution adopted by the
Council of the City of Absecon at a
Regular Meeting held January 18th, 2024**

**ATTEST: _____
Carie A. Crone, RMC, Municipal Clerk**

CITY OF ABSECON

RESOLUTION 33-2024

**A RESOLUTION AUTHORIZING THE SUBMISSION OF THE CITY OF
ABSECON'S TONNAGE GRANT APPLICATION FOR THE YEAR 2023 TO
THE NEW JERSEY DEPARTMENT OF ENVIRONMENTAL PROTECTION**

WHEREAS, The Mandatory Source Separation and Recycling Act, P.L. 1987, c.102, has established a recycling fund from which tonnage grant may be made to municipalities in order to encourage local source separation and recycling programs; and

WHEREAS, it is the intent and the spirit of the Mandatory Source Separation and Recycling Act to use the tonnage grants to develop new municipal recycling programs and to continue and to expand existing programs; and

WHEREAS, the New Jersey Department of Environmental Protection has promulgated recycling regulations to Implement the Mandatory Source Separation and Recycling Act; and

WHEREAS, the recycling regulations impose on municipalities certain requirements as a condition for applying for tonnage grants, including but not limited to, making and keeping accurate, verifiable records of materials collected and claimed by the municipality; and

WHEREAS, a resolution authorizing this municipality to apply for the 2023 Recycling Tonnage Grant will memorialize the commitment of this municipality to recycling and to indicate the assent of the Municipal Council of the City of Absecon to the efforts undertaken by the municipality and the requirements contained in the Recycling Act and recycling regulations.

WHEREAS, such a resolution should designate the individual authorized to ensure the application is properly completed and timely filed.

NOW, THEREFORE BE IT RESOLVED by the Municipal Council of the City of Absecon hereby endorses the submission of the recycling tonnage grant application to the New Jersey Department of Environmental Protection and designates Robert Battista, Recycling Coordinator, to ensure that the application is properly filed.

BE IT FURTHER RESOLVED that the monies received from the recycling tonnage grant be deposited in a dedicated recycling trust fund to be used solely for the purpose of recycling.

Dated: January 18th, 2024

**This is to certify that this is a true
Copy of a Resolution adopted by the
Council of the City of Absecon at a
regular meeting held January 18th, 2024**

ATTEST: _____
Carie A. Crone, RMC, Municipal Clerk

CITY OF ABSECON

RESOLUTION 34-2024

A RESOLUTION AUTHORIZING THE TAX COLLECTOR TO PRORATE AND CANCEL 4TH QUARTER TAXES OF 2023 AND CANCEL THE 2024 PRELIMINARY ON THE PROPERTY LOCATED AT 1009 CARALENA CT. (BLOCK 2, Lot 6.05)

WHEREAS, the Tax Collector, by letter attached, has notified City Council of a need to prorate and cancel the property taxes for 33 days of exemption for the 4th quarter and cancel the 2024 Preliminary in the amount listed below, for the property located at 1009 Caralena Court (Block 2, Lot 6.05), in the name of Wendall Archambo.

WHEREAS, the property is owned by an Exempt Veteran.

NOW, THEREFORE, BE IT RESOLVED by the Council of the City of Absecon that the amounts to be cancelled are as listed:

Block	Lot	Property Location	Property Owner	Tax Quarter	Cancel
2	6.05	1009 Caralena Court	Archambo, Wendall	4 th /2023	777.98
				1 st /2024	2,110.94
				2 nd /2024	2,110.93

NOW, THEREFORE, BE IT FURTHER RESOLVED by the Council of the City of Absecon that:

1. The Tax Collector be authorized and directed to cancel taxes as stated above on the listed property.

Dated: January 18th, 2024

**This is to certify that this is a true
Copy of a Resolution adopted by the
Council of the City of Absecon at a
regular meeting held January 18th, 2024**

**ATTEST: _____
Carie A. Crone, RMC, Municipal Clerk**

CITY OF ABSECON

Municipal Complex
500 Mill Rd.
ABSECON, NJ 08201



Absecon Absolutely!

Jessica A. Snyder, CTC
Tax Collector

Phone (609) 641-0663 ext. 116
Fax (609) 645-5098

December 27, 2023

Mayor & City Council
500 Mill Road
Absecon, NJ 08201

Dear Members of City Council,

Please have a resolution drawn up to prorate and cancel the property taxes for 33 days of exemption for the 4th quarter. Please also cancel the 2024 Preliminary in the amounts listed below. The following property is owned by Exempt Veteran per the Tax Assessor.

Block	Lot	Property Location	Property Owner	Tax Quarter	Cancel
2	6.05	1009 Caralena Court	Archambo, Wendall	4 th / 2023	777.98
				1 st / 2024	2,110.94
				2 nd / 2024	2,110.93

No refund is due to the property owner for this resolution request.

Sincerely,

Jessica A. Snyder, CTC
Tax Collector

cc: Wendall Archambo

CITY OF ABSECON

RESOLUTION 35-2024

**A RESOLUTION AUTHORIZING THE TAX COLLECTOR TO PRORATE AND
REFUND 3rd QUARTER TAXES OF 2023 AND CANCEL AND REFUND 4TH
QUARTER AND THE 2024 PRELIMINARY ON THE PROPERTY LOCATED AT
1 CLARIDGE COURT (BLOCK 35, Lot 7)**

WHEREAS, the Tax Collector, by letter attached, has notified City Council of a need to prorate and refund taxes for the 3rd quarter and cancel and refund 4th quarter as well as the 2024 Preliminary in the amount listed below, for the property located at 1 Claridge Court (Block35, Lot 7), in the name of Joseph Bonds.

WHEREAS, the property is owned by an Exempt Veteran.

NOW, THEREFORE, BE IT RESOLVED by the Council of the City of Absecon that the amounts to be cancelled are as listed:

Block	Lot	Property Location	Property Owner	Total Refund
35	7	1 Claridge Court	Bods, Joseph	2,463.55

NOW, THEREFORE, BE IT FURTHER RESOLVED by the Council of the City of Absecon that:

1. The Tax Collector be authorized and directed to cancel taxes as stated above on the listed property.
2. The Chief Financial Officer be authorized and directed to refund the amount listed above to Joseph Bonds, 1 Claridge Court, Absecon, NJ 08201

Dated: January 18th, 2024

**This is to certify that this is a true
Copy of a Resolution adopted by the
Council of the City of Absecon at a
regular meeting held January 18th, 2024**

**ATTEST: _____
Carie A. Crone, RMC, Municipal Clerk**

CITY OF ABSECON

Municipal Complex

500 Mill Rd.

ABSECON, NJ 08201



Absecon Absolutely!

Jessica A. Snyder, CTC
Tax Collector

Phone (609) 641-0663 ext. 116

Fax (609) 645-5098

December 21, 2023

Mayor & City Council
500 Mill Road
Absecon, NJ 08201

Dear Members of City Council,

Please have a resolution drawn up to prorate the property taxes for 1 day for the 3rd quarter and refund **\$27.03**. Please also cancel and refund **\$2,436.52** for the 4th quarter as well as the 2024 Preliminary. The following property is owned by Exempt Veteran.

Block	Lot	Property Location	Property Owner	Total Refund
35	7	1 Claridge Court	Bonds, Joseph	\$2,463.55

Please refund to the property owner at the address listed above.

Sincerely,

Jessica A. Snyder, CTC

Jessica A. Snyder, CTC
Tax Collector

CITY OF ABSECON

RESOLUTION 36-2024

**A RESOLUTION EXTENDING THE GRANT AGREEMENT TERM WITH
THE STATE OF NJ LOCAL EFFICIENCY ACHIEVEMENT PROGRAM (LEAP)**

WHEREAS, the State of New Jersey allocated \$3.8 million in Local Efficiency Achievement Program (LEAP) funds in 2022 to promote shared service initiatives among peer local units across New Jersey; and

WHEREAS, the Department of Community Affairs, Division of Local Government Services (DLGS) administers the LEAP grant program and provides reimbursement for qualifying expenses incurred in the implementation of a local or regional service agreements, or for the coordination of programs and services authorized under the Uniform Shared Services and Consolidation Act (N.J.S.A. 40A:65-1 et seq.); and

WHEREAS, on August 9 2022, the State of NJ DCA/DLGS and the City of Absecon executed a LEAP agreement, #I-2022-2023-01) with a term of July 1, 2022 to December 31, 2023, and

WHEREAS, the City of Absecon has experienced delays with fiber circuit internet service contract due to fiber installation construction project delays; and

WHEREAS, the City of Absecon has requested an extension to the term of the grant (#1-2022-2023-01) and remains committed to continuing to identify and achieve greater efficiencies and enhancing the quality of services within its borders; and

WHEREAS, the Acting Commissioner, Director has determined to extend the term of the grant period to July 1, 2024.

NOW, THEREFORE, BE IT RESOLVED by the Mayor and Governing Body of the City of Absecon, that the Governing Body does hereby request and accept the extension of the LEAP grant term to July 1, 2024.

Dated: January 18th, 2024

**This is to certify that this is a true
copy of a Resolution adopted by the
Council of the City of Absecon at a
Regular Meeting held January 18th, 2024**

ATTEST: _____
Carie A. Crone, RMC, Municipal Clerk

CITY OF ABSECON

RESOLUTION 37-2024

**A RESOLUTION AUTHORIZING THE MAYOR TO ENTER INTO A SECOND
AMENDED INTERLOCAL AGREEMENT WITH ATLANTIC COUNTY REGARDING
FLASHING SIGNAL EQUIPMENT AT VARIOUS LOCATIONS**

WHEREAS, the City of Absecon desires to enter into an inter-local agreement with Atlantic County for the installation and maintenance of flashing signal equipment at various locations; and

WHEREAS, the flashing signals will be located at each approach to the school zone area on Pitney Road and will have wireless communications features; and

WHEREAS, these signals will enhance safety awareness in the school zone; and

WHEREAS, the County shall be responsible for 100% of all costs associated with these improvements. The equipment shall be transferred to the City upon completion of the installation.

WHEREAS, the original agreement executed on July 18, 2019 needs to be amended to extend the term for a period of two (2) years to expire on February 2, 2026.

WHEREAS, all other terms and requirements of said Agreement shall remain in full force and effect.

NOW, THEREFORE, BE IT RESOLVED, by the Council of the City of Absecon that Mayor is hereby authorized to sign the second amended Interlocal Agreement with Atlantic County for the flashing signal equipment on Pitney Road.

Dated: January 18th, 2024

**This is to certify that this is a true
copy of a Resolution adopted by the
Council of the City of Absecon at a
Regular Meeting held January 18th, 2024**

**Attest: _____
Carie A. Crone, RMC, Municipal Clerk**

CITY OF ABSECON

RESOLUTION 38-2024

**A RESOLUTION AUTHORIZING THE MAYOR TO ENTER INTO A
LICENSE AGREEMENT/HOLD HARMLESS AGREEMENT WITH ATLANTIC
COUNTY CONCERNING STREETScape IMPROVEMENTS
WITHIN THE COUNTY RIGHT OF WAY OF NEW JERSEY AVENUE (CR 601)**

WHEREAS, the City of Absecon desires to enter into a License Agreement/Hold Harmless Agreement with Atlantic County concerning Streetscape Improvements within the County Right of Way of New Jersey Avenue (CR601); and

WHEREAS, the County currently owns a certain street and right-of-way located on New Jersey Avenue, identified as County Route 601; and

WHEREAS, the City has developed plans to construct streetscape improvements within the County right-of-way of New Jersey Avenue (CR 601), which will be consistent with previous phases of the City's Central Business District; and

WHEREAS, the County desires to accommodate the City's plans by authorizing the City to proceed with construction, operation and maintenance of the City's proposed improvements in consideration of the payment of \$1.00 by the City to the County.

NOW, THEREFORE, BE IT RESOLVED, by the Council of the City of Absecon that Mayor is hereby authorized to sign a License Agreement/Hold Harmless Agreement with Atlantic County concerning the Streetscape Improvements on New Jersey Avenue (CR 601).

Dated: January 18th, 2024

**This is to certify that this is a true
copy of a Resolution adopted by the
Council of the City of Absecon at a
Regular Meeting held January 18th, 2024**

**Attest: _____
Carie A. Crone, RMC, Municipal Clerk**

CITY OF ABSECON

RESOLUTION 39-2024

**A RESOLUTION AUTHORIZING THE MAYOR AND OTHER CITY
OFFICIALS TO EXECUTE A 2024 SAFETY CONTRACT WITH THE
ATLANTIC COUNTY MUNICIPAL JOINT INSURANCE FUND**

WHEREAS, the City of Absecon, ("City") is a member of the Atlantic County Joint Insurance Fund ("ACJIF"); and

WHEREAS, the City recognizes the role that an effective safety program plays in lowering employee injury rates, reducing lost time for accidents and cutting insurance costs, all of which contribute to greater employee safety and lower tax rates; and

WHEREAS, to that end, the City and the ACJIF desire to enter into a 2024 Safety Contract which sets forth specific steps which the City will undertake in calendar year 2024 to promote employee safety.

NOW THEREFORE, BE IT RESOLVED by the City Council of the City of Absecon, that the Mayor and other City Officials of JIF Safety Committee are hereby authorized to enter into a 2024 Safety Contract with ACJIF.

Dated: January 18th, 2024

**This is to certify that this is a true
copy of a Resolution adopted by the
Council of the City of Absecon at a
Regular Meeting held January 18th, 2024.**

**ATTEST: _____
Carie A. Crone, RMC, Municipal Clerk**

CITY OF ABSECON

RESOLUTION 40-2024

**A RESOLUTION AUTHORIZING THE TRANSFER OF APPROPRIATION
RESERVES IN THE 2023 LOCAL MUNICIPAL BUDGET PER N.J.S.A. 40A: 4-59**

WHEREAS, N.J.S.A. 40A: 4-59 allows transfers to be made from unexpended balances to balances, which are expected to be insufficient during the first (3) months of the preceding budget year.

NOW, THEREFORE, BE IT RESOLVED by the Mayor and Council of the City of Absecon that transfers are made in the amount of \$16,000.00 and that said transfers be made in the 2023 budget as follows:

	<u>TO</u>	<u>FROM</u>
Police S&W	16,000.00	
Engineering OE		16,000.00
	<u>\$ 16,000.00</u>	<u>\$ 16,000.00</u>

Dated: January 18th, 2024

**This is to certify this is a true copy of
a Resolution adopted by the Council
of the City of Absecon at a regular
meeting held on January 18th, 2024**

**Attest: _____
Carie A. Crone, RMC, Municipal Clerk**

CITY OF ABSECON

RESOLUTION 41-2024

A RESOLUTION TO RECONSTITUTE THE GREEN TEAM ADVISORY COMMITTEE FOR THE CITY OF ABSECON

WHEREAS, The City of Absecon strives to save tax dollars, assure clean air and water, and improve working and living environments to build a community that is sustainable economically, environmentally and socially; and

WHEREAS, the City of Absecon wishes to build a model of government which benefits our residents now and far into the future with green community initiatives which are easy to replicate and affordable to implement; and

WHEREAS, in an attempt to focus attention on "Green" issues, the City Council wishes to reconstitute the Green Team Advisory Committee (GTA); and

NOW THEREFORE BE IT RESOLVED, by the City Council of the City of Absecon that we do hereby reconstitute the Green Team Advisory Committee consisting of ten members who shall be appointed annually by the City Council, but whose next term of appointment shall be through December 31, 2024.

NOW THEREFORE BE IT FURTHER RESOLVED, by the City of Absecon that the Mission, Goals and Objectives for the GTA through December 31, 2024 are established as follows:

Mission:

To encourage the people and institutions of Absecon to cooperatively adopt fundamental principles of sustainability and sustainable development, and to develop policies and practices that fulfill those principles.

Goals:

1. Achieve sustainability through sustainable development by utilizing the triple bottom line approach. Where the economy, society, and environment meet sustainability is achieved.
2. Identify existing initiatives and programs that the community is already doing that support sustainability.
3. To pursue initiatives that will encourage residents and businesses within Absecon to take steps toward energy efficiency and conservation and to develop sustainable practices.
4. To attain Sustainable Jersey Certification.

NOW THEREFORE BE IT FINALLY RESOLVED, by the City Council of the City of Absecon that the following persons are hereby appointed to the GTA for the remainder of 2024 and are eligible to serve until replaced through an updated resolution.

Nick LaRotonda, Council Liaison
Stephen Light, Council Liaison
Lloyd Jones, Municipal Liaison

Alexander Perri, Chairperson
Christina Seel, Vice Chairperson
Jennifer Stairs, Community Garden Coordinator
Greg Seher
Michael Celestino
Reed Moscatello
Jackie Hall
Peg Lijoi
Leonard Walk
Rorie Herndon

Dated: January 18th, 2024

**This is to certify that this is a true
copy of a Resolution adopted by the
Council of the City of Absecon at a
Regular Meeting held January 18th, 2024**

**ATTEST: _____
Carie A. Crone, RMC, Municipal Clerk**

CITY OF ABSECON

RESOLUTION 42-2024

**A RESOLUTION RECOGNIZING THE MEMBERS OF THE ABSECON
GREEN TEAM, A TASK FORCE FOR SUSTAINABLE ABSECON**

WHEREAS, the Absecon Green Team is a community organization dedicated to achieving certification from the Sustainable Jersey Program; and

WHEREAS, the Absecon Green Team has made great strides in moving the City of Absecon toward sustainable living; and

WHEREAS, there are many members who have proven their dedication to the mission of the Absecon Green Team, and continue to put in countless hours and are deserving of recognition by Resolution for their effort.

NOW THEREFORE BE IT RESOLVED, by the City Council of the City of Absecon, that the following persons be recognized for their volunteer contributions to the Absecon Green Team for the year 2023.

Team Members:

Rich Derose, Council Liaison
Steve Light, Council Liaison
Alexander Perri, Chairperson
Christina Seel, Vice Chairperson
Jennifer Stairs, Community Garden Coordinator
Greg Seher, Advisory Committee Member
Michael Celestino, Advisory Committee Member
Reed Moscatello, Advisory Committee Member
Peg Lijoi, Advisory Committee Member
Leonard Walk, Advisory Committee Member
Cole Branson, Advisory Committee Member
Rorie Herndon, Advisory Committee Member

Eric Herndon
Jackie Hall
Tracy Morgan
Ashley Pushman
Denise Lenz
Marianne Hicks
Pat Seel
Hannah Link-Fitzgerald

Dated: January 18th, 2024

**This is to certify that this is a true
copy of a Resolution adopted by the
Council of the City of Absecon at a
Regular Meeting held January 18th, 2024.**

ATTEST: _____
Carie A. Crone, RMC, Municipal Clerk

CLERK'S MONTHLY REPORT

DECEMBER, 2023

	MONTHLY RECEIPTS		YEAR TO DATE RECEIPTS
YARD SALE PERMITS	5.00		295.00
MARRIAGE LICENSES	56.00		1,008.00
DEATH CERTIFICATES	-		570.00
MARRIAGE LICENSE COPIES	165.00		1,815.00
DOMESTIC PART. LICENSE	-		-
DOMESTIC PART. COPIES	-		-
CEREMONY FEES	75.00		425.00
RAFFLE LICENSES	60.00		940.00
BIRTH CERTIFICATES	-		-
MERCANTILE LICENSES	150.00		15,300.00
CANNABIS APPLICATION	-		200.00
EXCAVATION PERMITS	2,690.00		17,670.00
COPIES	-		42.52
TAXI LICENSES	-		-
LIQUOR LICENSES	250.00		10,950.00
PLANNING FEES	-		4,810.00
ZONING FEES	300.00		300.00
MISC	-		597.30
TOTAL	3,751.00		56,422.82
BOAT RAMP PERMITS	500.00		29,950.00
ANIMAL CONTROL	-		1,239.00
TOTAL CLERK'S OFFICE	4,251.00		87,611.82

CITY OF ABSECON CITY
CONSTRUCTION OFFICE CODE ENFORCEMENT
MONTHLY REPORT

DECEMBER 2023

	Month		Year to Date	
	# Permits	Fees	# Permits	Fees
Building Permits	13	\$ 3,688.00	149	\$ 71,427.00
Electrical Permits	18	\$ 2,660.00	229	\$ 29,572.00
Elevator Permits	0		0	\$ -
Fire Permits	7	\$ 500.00	85	\$ 11,800.00
Plumbing Permits	23	\$ 1,985.00	101	\$ 14,116.00
Mechanical Permits	8	\$ 810.00	117	\$ 11,430.00
Certificates of Occupancy	1	\$ 75.00	18	\$ 1,950.00
DCA Fees	45	\$ 910.00	377	\$ 12,334.00
Contractor Licenses	0		16	\$ 400.00
Zoning Permits	6	\$ 255.00	94	\$ 3,835.00
CCO Resales	6	\$ 410.00	158	\$ 11,685.00
Commercial CCO, Rental	0		0	\$ 1,640.00
Rental Inspections	5	\$ 425.00	147	\$ 12,600.00
Certificates of Compliance	0		4	\$ 200.00
Misc.	2	\$ 125.00	6	\$ 2,125.00
Penalty	0		1	\$ -
Admin Fees	0		0	\$ 1,072.00

Total Fees	\$ 11,843.00	183,466.00
Total Paid Out	\$ 910.00	12,334.00
Total Net Fees	\$ 10,933.00	171,122.00
Total Construction Cost	\$ 1,165,222.00	9,321,124.72

Respectfully Submitted:

Kimberly Kollman / Technical Assistant

CC: City Admin. / CFO / City Clerk / Construction Official

REPORT ID : TFC5337
RUN DATE : 01/07/2024
RUN TIME : 02:14

NJ AUTOMATED MUNICIPAL SYSTEM
MONTHLY CASHBOOK REPORT
ABSECON MUNICIPAL COURT
FOR THE MONTH OF DECEMBER 2023

PAGE: 8

PART 4 - DISBURSEMENT CHECKS

MAKE CHECK PAYABLE TO:	CHECK AMOUNT	ADDRESS	CHECK NUMBER	CROSS-REF W/BANKSTMT
2 - TREASURER, STATE OF NEW JERSEY RE: AUTOMATION FEE - AF ATS MODERNIZATION FUND - AM	\$142.00 \$213.00 \$355.00	AOC ATS SURCHARGE SECTION P.O. BOX 980 TRENTON, NJ 08625	DO NOT SEND CHECK- SENT VIA ACH	
3 - TREASURER, <u>Atlantic</u> COUNTY OF RE: TITLE 39 SPLIT & VIDEO SURCHARGE (VY)	\$3,113.28	COUNTY TREASURER	1796	
4 - TREASURER, CITY OF <u>Absecon</u> RE: TITLE 39 SPLIT, CRIMINAL FINES, COSTS, LOCAL PARKING, CONTEMPT, CRIMINAL BAIL FORFEITURE, ADDITIONAL PENALTIES, GENERAL FEES, UNREFUNDED OVERPAYMENTS, PUBLIC DEFENDER, PLAINTIFF COSTS, SPINAL MUNICIPAL, DWI SURCHARGE, UC CODE, VIDEO SURCHARGE (VM) & SANCTIONS	\$6,247.11	CITY OF <u>Absecon</u>	1797	
5 - TREASURER, CITY OF <u>Absecon</u> RE: PARKING OFFENSES ADJUDICATION ACT (\$2.00 FTA FEE - PA)	\$2.00	CITY OF <u>Absecon</u>	1798	
6 - TREASURER, STATE OF NEW JERSEY RE: VCCB, VAF, CF	\$150.00	VICTIMS OF CRIME COMPENSATION BOARD P.O. BOX 34090 NEWARK, NJ 07189-0090	DO NOT SEND CHECK- SENT VIA ACH	
7 - TREASURER, STATE OF NEW JERSEY RE: DEDR	\$.00	GOVERNOR'S COUNCIL ON ALCOHOLISM/ DRUG ABUSE P.O. BOX 345 TRENTON, NJ 08625	DO NOT SEND CHECK- SENT VIA ACH	
8 - TREASURER, STATE OF NEW JERSEY RE: STATE LAB FEES - FLF (SL)	\$.00	GOVERNOR'S COUNCIL ON ALCOHOLISM/ DRUG ABUSE P.O. BOX 345 TRENTON, NJ 08625	DO NOT SEND CHECK- SENT VIA ACH	
9 - TREASURER, COUNTY OF RE: COUNTY LAB FEES - (CL)	\$.00	N/A		

January 8, 2024
04:10 PM

City of Absecon
Cash Receipts Totals from 12/01/23 to 12/31/23

Page No: 1

Range: Block: First to Last Range of Util Accounts: First to Last
Lot:
Qual:
Range of Codes: 001 to 052 Range of Years: First to 2024 Range of Periods: 1 to 12
Range of Batch Ids: First to Last Range of Dates: 12/01/23 to 12/31/23
Range of Sections: First to Last Name to Print: Bill To
Range of Spec Tax Codes: First to Last Print Ref Num: N Print Utility w/Block/Lot/Qual: N
Payment Type Includes: Tax: Y Sp Charges: Y Lien: Y Sp Assmnt: Y Sewer: Y
Voucher Agency: Y Animal: N Misc: Y
Payment Method Includes: Cash: Y Check: Y Credit: Y Voucher: N
Range of Installment Due Dates: First to Last
Print Only Miscellaneous w/Block/Lot/Qual: N Sort Miscellaneous Payments by Block/Lot/Qual/Utility Account: N
Print Only Miscellaneous w/Utility Id: N

Code	Description	Count	Arrears/Other	Principal	2022	2023	2024	Pnlty/Intr	Total
001	Property Taxes	340	0.00	0.00	0.00	173,248.75	142,511.48	5,745.80	321,506.03
038	Taxes - Subsequent	5	0.00	0.00	0.00	4,568.28	0.00	202.61	4,770.89
	Tax Payments	345	0.00	0.00	0.00	177,817.03	142,511.48	5,948.41	326,276.92
002	Sewer Rental	2199	353.00	0.00	0.00	36,160.50	343,234.87	1,717.52	381,465.89
037	Sewer - Subsequent	4	0.00	0.00	0.00	594.00	0.00	30.00	624.00
	Sewer Payments	2203	353.00	0.00	0.00	36,754.50	343,234.87	1,747.52	382,089.89
028	DUPL.REDEMPTION CER	6	200.00	0.00	0.00	0.00	0.00	0.00	200.00
031	SEWER LATERAL	1	500.00	0.00	0.00	0.00	0.00	0.00	500.00
	Misc Payments	7	700.00	0.00	0.00	0.00	0.00	0.00	700.00
Payments Total:		2555	1,053.00	0.00	0.00	214,571.53	485,746.35	7,695.93	709,066.81
Cash O/S Total:		0	0.00	0.00	0.00	0.00	0.00	0.00	0.00
NSF Reversals Total:		0	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Total:		2555	1,053.00	0.00	0.00	214,571.53	485,746.35	7,695.93	709,066.81
Total Cash:		40,269.15							
Total Check:		628,054.47							
Total Credit:		40,743.19							
Sewer Overpayments			353.00						
Total Overpayments			353.00						

January 17, 2024
03:29 PM

City of Absecon
Bill List By Vendor Id

Page No: 1

P.O. Type: All Include Project Line Items: Yes Open: N Paid: N Void: N
Range: First to Last Rcvd: Y Held: Y Aprv: N
Format: Condensed Bid: Y State: Y Other: Y Exempt: Y
Vendors: All Include Non-Budgeted: Y
Rcvd Batch Id Range: First to Last

Vendor #	Name	PO #	PO Date	Description	Status	Amount	Void Amount	Contract	PO Type
1068	ALISON SHENOT	23-01395	12/15/23	RESOLUTION 147	Open	3,996.00	0.00		
1070	MORRISON, LOUISE	23-01425	12/29/23	SEWER REFUND	Open	99.00	0.00		
9230	ROY TALLEY	24-00017	01/17/24	PETTY CASH REIMBURSEMENT	Open	176.99	0.00		
9476	WITMER PUBLIC SAFETY GROUP INC	23-01264	11/06/23	HOLSTER	Open	2,392.63	0.00		
9571	JENNIFER KELLY, PH.D., ABPP	23-01417	12/28/23	PROFESSIONAL SERVICES	Open	990.00	0.00		
A0002	ARIZENT	23-01415	12/26/23	LEGAL ADVERTISING BOND BUYER	Open	2,394.00	0.00		
A0003	ACUA	23-01433	12/29/23	DEC. 2023 TIP/RECYCLING/FUEL	Open	73,651.29	0.00		
A0005	ABSECON BOARD OF EDUCATION	24-00034	01/17/24	JANUARY SCHOOL PAYMENT 2024	Open	1,034,941.17	0.00		
A0009	ANIMAL CONTROL OF S.J.	23-01430	12/29/23	DECEMBER 2023 SERVICES	Open	700.00	0.00		
A0034	ABSECON CITY PAYROLL ACCOUNT	24-00030	01/17/24	PP1 1/4/24	Open	172,465.35	0.00		
A0081	AFTERMATH SERVICES LLC	23-01439	12/29/23	PROFESSIONAL SERVICES	Open	300.00	0.00		
A0209	ADVANCE AUTO PARTS	24-00008	01/17/24	SUPPLIES	Open	24.81	0.00		
A0253	ATLANTIC CITY ELECTRIC	23-01435	12/28/23	DECEMBER 2023 UTILITY	Open	31,028.13	0.00		
B0119	BLANEY, DONOHUE, ET AL	24-00015	01/17/24	LEGAL SERVICES 11/7-12/29/23	Open	9,635.00	0.00		
C0027	COLLIERS ENGINEERING	24-00018	01/17/24	PROFESSIONAL SERVICES	Open	6,458.47	0.00		
C0044	CARDMEMBER SERVICE	23-01414	12/21/23	WELLNESS	Open	300.00	0.00		

January 17, 2024
03:29 PM

City of Absecon
Bill List By Vendor Id

Page No: 2

Vendor #	Name	Status	Amount	Void Amount	Contract	PO Type
PO #	PO Date Description					
C0044	CARDMEMBER SERVICE	Continued				
24-00032	01/17/24 SUPPLIES	Open	2,360.18	0.00		
			2,660.18			
C0098	CROWN CASTLE FIBER LLC					
24-00006	01/17/24 1/1/24-1/31/24 SERVICES	Open	1,150.00	0.00		
C0128	CLEGG'S GARAGE INC					
24-00012	01/17/24 REPAIRS TO LEAFER	Open	154.31	0.00		
24-00026	01/17/24 VEHICLE MAINTENANCE	Open	3,034.57	0.00		
			3,188.88			
C0180	CASA PAYROLL SERVICES					
23-01422	12/29/23 PAYROLL PROCESSING	Open	1,214.00	0.00		
24-00031	01/17/24 PAYROLL PROCESSING	Open	253.40	0.00		
			1,467.40			
C0208	CME ASSOCIATES					
24-00023	01/17/24 PROFESSIONAL SERVICES	Open	304.50	0.00		
D0052	DEPOSITORY TRUST					
24-00024	01/17/24 BOND INTEREST	Open	136,621.89	0.00		
E0001	ESO SOLUTIONS, INC					
24-00005	01/17/24 ER-ROVER SUBSCRIPTION	Open	300.00	0.00		
E0002	EDMUNDS & ASSOCIATES INC					
24-00029	01/17/24 SOFTWARE MAINTENANCE	Open	13,709.79	0.00		
E0070	ED & GENE'S KING TIRE LLC					
23-01424	12/29/23 VEHICLE MAINTENANCE	Open	1,561.59	0.00		
23-01438	12/29/23 VEHICLE MAINTENANCE	Open	966.82	0.00		
24-00022	01/17/24 VEHICLE MAINTENANCE	Open	80.00	0.00		
			2,608.41			
G0001	GLENN INSURANCE INC					
24-00028	01/17/24 FIDELITY BOND	Open	250.00	0.00		
G0028	G.M. WHITE					
23-00490	05/18/23 PEDESTRAIN CROSSING SIGNS	Open	24,500.00	0.00		
H0010	BETTY HOWELL					
23-01372	12/14/23 REFUND	Open	21.17	0.00		
H0066	THE HOME DEPOT CREDIT SERVICE					
23-01426	12/29/23 SUPPLIES	Open	331.89	0.00		
H0073	HR DIRECT					
24-00011	01/17/24 2024 ATTENDANCE CALENDERS	Open	72.33	0.00		
H0083	HORIZON BLUE CROSS					
24-00002	01/17/24 JANUARY 2024 DENTAL	Open	3,934.99	0.00		

January 17, 2024
03:29 PM

City of Absecon
Bill List By Vendor Id

Page No: 3

Vendor #	Name	PO #	PO Date	Description	Status	Amount	Void Amount	Contract	PO Type
L0016	FRANK J. LENTZ, ESQ	23-01428	12/29/23	DECEMBER 2023 PUBLIC DEFENDER	Open	600.00	0.00		
L0064	LINCOLN FINANCIAL ADVISORS	23-01443	12/29/23	LOSAP CONTRIBUTION	Open	602.31	0.00		
L0086	TELESYSTEM	23-01432	12/29/23	DECEMBER 2023 MONTHLY BILLING	Open	3,469.71	0.00		
M0004	MOBILE DREDGING & VIDEO PIPE	23-01123	10/03/23	PROFESSIONAL SERVICES	Open	35,666.00	0.00		B
M0153	MUNIDEX INC	24-00027	01/17/24	2024 VITAL STATISTICS	Open	628.20	0.00		
N0091	NETWORK CONNECTIVITY, INC.	24-00036	01/17/24	JANUARY 2023 SERVICES	Open	3,645.74	0.00		
O0008	OYSTER BAY CONDO ASSOC	23-01442	12/29/23	REIMBURSEMENT 2023 STREETLIGHT	Open	10,343.96	0.00		
O0014	ONSOLVE, LLC	24-00004	01/17/24	EMERGENCY NOTIF SERVICE 2024	Open	658.82	0.00		
O0031	MICHAEL G. O'HAGAN	24-00020	01/17/24	REIMBURSEMENT	Open	260.00	0.00		
P0001	PRESS OF ATLANTIC CITY	23-01436	12/31/23	LEGAL ADVERTISEMENT	Open	36.96	0.00		
P0014	PEDRONI FUEL CO	23-01420	12/29/23	GASOLINE AND DIESEL	Open	1,724.03	0.00		
		23-01441	12/29/23	DIESEL	Open	<u>1,025.11</u>	0.00		
						2,749.14			
S0011	A E STONE INC	24-00009	01/17/24	5 TONS ASPHALT	Open	458.22	0.00		
S0019	SOUTH JERSEY GAS CO.	23-01427	12/29/23	DECEMBER 2023 UTILITY	Open	2,739.77	0.00		
S0027	SOUTHERN COASTAL REGIONAL	24-00001	01/17/24	JANUARY 2024 HEALTH BENEFITS	Open	84,822.00	0.00		
S0136	SUPPLY IT ALL	23-01402	12/18/23	C- FOLD & TOILET PAPER	Open	969.84	0.00		
S0189	STATE TOXICOLOGY LABORATORY	23-01447	12/29/23	RANDOM TESTING	Open	45.00	0.00		
T0044	TREASURER	24-00021	01/17/24	4TH QTR DCA STATE TRAINING FEE	Open	2,058.00	0.00		

Vendor #	Name	PO #	PO Date	Description	Status	Amount	Void Amount	Contract	PO Type
T0044	TREASURER				Continued				
		24-00025	01/17/24	NOV DOG REPORT	Open	4.20	0.00		
						2,062.20			
T0092	TOSHIBA BUSINESS SOLUTIONS,USA								
		23-01440	12/29/23	COPIER COUNT/MAIN. 9/18-12/17	Open	7.96	0.00		
		24-00019	01/17/24	COPIER COUNT/MAIN. 10/3-1/5	Open	558.30	0.00		
						566.26			
T0096	TOSHIBA FINANCIAL SERVICES								
		23-01444	12/29/23	COPIER LEASE	Open	41.39	0.00		
T0105	TELVUE CORP.								
		24-00016	01/17/24	WEBUS SUPPORT	Open	600.00	0.00		
T0106	TACTICAL PUBLIC SAFETY, LLC								
		23-01358	12/06/23	XG15 BATTERIES	Open	478.80	0.00		
T0110	CARL N. TRIPICIAN, ESQUIRE								
		23-01429	12/29/23	DECEMBER 2023 PROSECUTOR	Open	1,800.00	0.00		
U0021	UNITED METHODIST CHURCH								
		23-01423	12/29/23	NOVEMBER 2023 SENIOR SERVICES	Open	2,123.16	0.00		
V0012	VISION SERVICE PLAN (EA)								
		23-01445	01/11/24	DECEMBER 2023 CLAIMS	Open	844.00	0.00		
		24-00003	01/17/24	JANUARY 2024	Open	230.19	0.00		
						1,074.19			
V0022	VERIZON								
		23-01437	12/29/23	DECEMBER 2023 SERVICES	Open	149.72	0.00		
V0035	VAL-U AUTO PARTS								
		24-00014	01/17/24	AUTOMOTIVE SUPPLIES	Open	294.90	0.00		
W0009	JESSE WESTON								
		24-00033	01/17/24	GROUND MAINT @ LIBRARY	Open	759.00	0.00		
W0011	WITMER PUBLIC SAFETY GROUP INC								
		23-01418	12/28/23	NIGHTSTICK	Open	744.89	0.00		
W0044	WASZEN BROTHERS								
		24-00010	01/17/24	TOILET RENTAL & PUMP RENTAL	Open	2,649.33	0.00		
Total Purchase Orders:	68	Total P.O. Line Items:	0	Total List Amount:	1,691,413.78	Total Void Amount:	0.00		